

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

SMALL SUSAN S ETALS /Russ Doucette

Located at

0 MAYFIELD ST (39)

PERMIT ID: 2014-00663

ISSUE DATE: 09/12/2014

CBL: 145 B032001

has permission to **New Single Family Home (40' x 38') with attached garage.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ David Petruccelli

Fire Official

/s/ Tammy Munson

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

Classification:

One or Two Family Dwellings

ENTIRE

NFPA 2009

PERMIT ID: 2014-00663

Located at: 0 MAYFIELD ST (39)

CBL: 145 B032001

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Setbacks and Footings Prior to Pouring
Foundation/Backfill
Close-in Plumbing/Framing
Electrical Close-in
Electrical Service
Certificate of Occupancy/Final
Final - Fire
Final - Electric

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2014-00663	Date Applied For: 04/07/2014	CBL: 145 B032001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Single Family on lot split from 29 Mayfield Street		Proposed Project Description: New Single Family Home (40' x 38') with attached garage.		
Dept: Zoning		Status: Approved w/Conditions	Reviewer: Ann Machado	Approval Date: 09/02/2014
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
<ol style="list-style-type: none"> 1) The ten foot by twelve foot shed must be relocated to where shown on the site plan before the certificate of occupancy is issued. 2) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work. 3) Separate permits shall be required for future decks, sheds, pools, and/or garages. 4) With the issuance of this permit and the certificate of occupancy, this property shall remain a single family dwelling. Any change of use shall require a separate permit application for review and approval. 5) The certificate of occupancy cannot be issued until our office receives a recorded deed for this property only. 				
Dept: Building		Status: Approved w/Conditions	Reviewer: Tammy Munson	Approval Date: 07/08/2014
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
<ol style="list-style-type: none"> 1) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process. 2) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work. 3) The design load spec sheets for any engineered beam(s) / Trusses must be submitted to this office. 4) Egress size windows are required (1) in each bedroom per IRC Sec. R310 5) The basement is NOT approved as habitable space. In order to change the use of this space, a code compliant Emergency Escape and Rescue Opening shall be installed per IRC Sec. R310. A separate permit is required. 6) Hardwired photoelectric interconnected battery backup smoke detectors shall be installed in all bedrooms, protecting the bedrooms, and on every level. The same is required for existing buildings, where permanent wiring is feasible; or at the very least battery operated smoke detectors are required. Verification of this will be upon inspection. 7) Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to bedrooms. That detection must be powered by the electrical service (plug-in or hardwired) in the building and battery. 8) A copy of the enclosed chimney or fireplace disclosure must be submitted to this office upon completion of the permitted work or for the Certificate of Occupancy. 9) Energy Code compliance shall be confirmed via a ResCheck or ComCheck, http://www.energycodes.gov/software.stm#tabs-2 certificate or alternate program standard for thermal envelope and MEP systems. 				
Dept: Fire		Status: Approved w/Conditions	Reviewer: David Petruccelli	Approval Date: 09/12/2014
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				

- 1) Single-station Carbon Monoxide (CO) alarms are required. They shall be powered by the building's electrical service with battery backup and shall be interconnected. CO alarms shall be installed in the following locations:
 - (1) Outside each separate dwelling unit sleeping area in the immediate vicinity of the bedrooms
 - (2) On every occupiable level of the dwelling unit, including basements, excluding attics and crawl spaces
- 2) A sprinkler system shall be installed in accordance with NFPA 13D. A no fee One- or Two-family CITY Fire Sprinkler Permit is required.
- 3) A copy of the State Sprinkler permit with RMS date and signature shall be provided prior to scheduling of the final inspection.
- 4) Single-station photoelectric smoke alarms are required. They shall be powered by the building's electrical service with battery backup and shall be interconnected. Smoke alarms shall be installed in the following locations:
 - (1) All sleeping rooms
 - (2) Outside each separate sleeping area, in the immediate vicinity of the sleeping rooms
 - (3) On each level of the dwelling unit, including basements.

Dept: DRC **Status:** Approved w/Conditions **Reviewer:** Philip DiPierro **Approval Date:** 09/12/2014

Note: **Ok to Issue:**

Conditions:

- 1) A sewer permit is required for your project. Please contact Carol Merritt at 874-8300, ext . 8822. The Wastewater and Drainage section of Public Services must be notified five (5) working days prior to sewer connection to schedule an inspector for your site.
- 2) A performance guarantee will be required to cover the cost of site work not completed due to seasonal conditions ie., finish grading, loaming, seeding, mulching, installation of street trees, etc. The performance guarantee must be reviewed, approved, and accepted by the Planning Authority prior to the release of a Temporary Certificate of Occupancy.
- 3) This site must comply with the Landscape Preservation Standards outlined in the Land Use Ordinance, section 14-526(b)2a, stating that a minimum of 30% of existing trees, ten (10) inches DBH or greater, within the required setback, must be preserved. Trees that are designated to be saved are to be protected during excavation and construction. Tree protection fencing is to be installed around the tree canopy drip line prior to the start of any excavation. Tree protection measures are to be inspected and maintained daily.
- 4) The applicant shall have a licensed surveyor install, prior to the issuance of any Certificate of Occupancy, permanent mounumentation/pins identifying property corners.
- 5) Erosion and Sedimentation control shall be established and inspected by the Development Review Coordinator prior to soil disturbance, and shall be done in accordance with Best Management Practices, Maine Department of Environmental Protection Technical and Design Standards and Guidelines. All Erosion and Sedimentation control measures must be inspected and maintained daily.
- 6) The Development Review Coordinator reserves the right to require additional lot grading or other drainage improvements as necessary due to field conditions.
- 7) All Site work (final grading, landscaping, loam and seed) must be completed prior to issuance of a certificate of occupancy.
- 8) The applicant must coordinate with the City's Corporation Counsel for the development and execution of the agreement and waiver of liability, for the turnaround to be used by the City in the applicant's driveway at the end of Mayfield Street. The agreement and waiver of liability must be reviewed and approved by the City, executed (and recorded at the registry of deeds if necessary) prior to the issuance of a temporary or permanent certificate of occupancy.
- 9) All damage to sidewalk, curb, street, or public utilities shall be repaired to City of Portland standards prior to issuance of a certificate of occupancy.
- 10) The Development Review Coordinator (874-8632) must be notified five (5) working days prior to date required for final site inspection. Please make allowances for completion of site plan requirements determined to be incomplete or defective during the inspection. This is essential as all site plan requirements must be completed and approved by the Development Review Coordinator prior to issuance of a Certificate of Occupancy. Please schedule any property closing with these requirements in mind.
- 11) Two (2) City of Portland approved species and size trees must be planted on your street frontage prior to issuance of a Certificate of Occupancy.
- 12) A revised survey, matching the metes and bounds description of the recorded "well and waterline" easement deed, must be submitted to, reviewed, and approved by the Planning Authority prior to the issuance of the temporary or permanent certificate of occupancy.
- 13) The site shall be developed and maintained as depicted in the approved site plan, written submission of the applicant, and these written conditions of approval. The modification of the approved site plan or alteration of a parcel which was the subject of site plan approval shall require the prior approval of a revised site plan by the Planning Authority.

14 A street opening permit(s) is required for your site. Please contact Carol Merritt ay 874-8300, ext. 8822. (Only excavators licensed by the City of Portland are eligible.)