

SECTION 07460 - SIDING

PART 1 - GENERAL

SUMMARY

This Section includes vinyl siding and vinyl soffit.

SUBMITTALS

Product Data: For each product indicated.

Samples: Full-size units of each type of siding and trim and in each color, texture, and pattern required.

PART 2 - PRODUCTS

SIDING

Formed-Vinyl Siding: Solid vinyl siding and accessories complying with ASTM D 3679.

Products: Subject to compliance with requirements, provide one of the following:

Alcoa Building Products; Silhouette - 0.044" thick.
Alside, Inc.; Odyssey Plus - 0.044" thick.
CertainTeed Corp., Vinyl Building Products Group; Rigidform 160.
Georgia-Pacific Corp.; Wyndham Lane - 0.045" thick.

Color and Texture: White, wood grain.

Pattern: Horizontal, traditional lap, 8 inch exposure in double 4 inch style.

SOFFIT

Vinyl Soffit: Perforated vinyl soffit and accessories complying with ASTM D 4477, perforated where indicated, 12-inch (305-mm) exposure in double 6-inch (152-mm) style.

Color and Texture: White, smooth.

ACCESSORIES

Siding Accessories: Provide starter strips, edge trim, window head flashing, corner cap, and other items as recommended by manufacturer for building configuration; match type of siding.

Fasteners: Noncorrosive aluminum siding nails, in sufficient length to penetrate a minimum of 1 inch (25 mm) into substrate. Provide prefinished fasteners in color to match siding where face nailing is unavoidable.

**RENOVATIONS TO THE CHILDREN'S CENTER
STEVENS AVE., PORTLAND, ME**

PART 3 - EXECUTION

INSTALLATION

Coordinate installation with flashings and other adjoining construction to ensure proper sequencing.

Center nails in elongated nailing slots without binding siding to allow for thermal movement. Overlap joints to shed water away from direction of prevailing wind.

Install vinyl siding, soffit, and accessories according to ASTM D 4756.

Install aluminum siding, soffit, and accessories according to AAMA 1402.

END OF SECTION 07460