

Starbucks – Drive Thru Wall Sign Details

ILLUMINATED DT WALL SIGN
 Qty. 1 SBC ADT-1862-RH

Sign Specifications:

- Cabinet
 - Fabricated .090" [2mm] aluminum housing painted black to match RAL 7021M with white end cap as shown.
 - Directional copy and chevrons backed up with .125" white polycarb. All polycarb face elements to be attached to aluminum face panel with weld studs.
 - Welded aluminum construction with no visible fasteners. Fasteners retaining the hinged face will be located on the bottom such that they are not visible. All fasteners used in the assembly of internal components shall be coated to prevent corrosion.
 - Internal structure of cabinet shall be per approved shop drawings.
 - Graphic elements are internally illuminated using GE Tetra MiniMax LED system or Starbucks approved equal. LEDs to be mounted on back panel with self-contained power supply. All electrical components are removable for service.

Regulatory:

- Sign must meet all regulations in the National Electric Code as well as any local or state electrical codes.
- As per NEC 600.6, sign is equipped with a service disconnect switch.
- Sign must be listed as an Electric Sign per Underwriters Laboratories UL 48 and/or CSA and bear the appropriate UL, CUL or CSA relevant certification marks.
- Primary power by electrical contractor per NEC.

Size	Sq. Ft. ¹	Sq. Ft. ²	Volts	Amps
18.50" (467mm)	5.97	9.25	120	0.85

¹ Reported as fabricated center part
² Reported as complete signage

COLOR LEGEND

PMS/PART	WWT/L
PMS 3425 C	3M 3630-76
RAL 7021M	3M 3630-22
PMS WHITE	3M 3630-20/77 25-10
PMS 369 C	NA
REFL. WHITE	3M 680-10

Service Position View

Section View at Installation Detail

ILLUMINATION VIEW

GE GEPS12-60 power supply or equal

Weatherproof disconnect switch with sealing boot

GE Tetra MiniMax LEDs or Starbucks approved equal

1/2" [13mm] wide black neoprene gasket around inside perimeter of filler

Scale: 3/4" = 1' (11x17 Paper) 7.96 S/F

Rev. 1

HILTON DISPLAYS
 125 HILLSIDE DRIVE • GREENVILLE SC 29607
 P 803.333.9133 • F 864.243.2264
 www.hiltondisplays.com

QID 17-38411

JOB NAME
Starbucks 11917

LOCATION
1080 Forest Ave.
Portland, ME 04103

CUSTOMER CONTACT

SALESMAN / PM
Joe Nolasco

DESIGNER
Jesse Black

DWG. DATE
08-24-17

REV. DATE / REVISION

SCALE
As Noted

FILE
2017/Starbucks/Portland ME/
17-38411/SB Portland ME.cdr

DESIGN SPECIFICATIONS ACCEPTED BY:

EST: CLIENT:
 SLS/PM: LANDLORD:

THE INTENT OF THIS DRAWING IS TO SHOW A CONCEPTUAL REPRESENTATION OF THE PROPOSED SIGNAGE. DUE TO VARIATIONS IN PRINTING PROCESSES AND SUBSTRATES, THE FINISHED PRODUCT MAY DIFFER SLIGHTLY FROM DRAWING.

UL Underwriters Laboratories Inc. **DRY SHARP**



Client & Location



Starbucks
 1080 Forest Ave
 Portland ME

Customer Approval Signature

Revisions

Drawing ID

Date
9.15.17

Page #
WVO #