

# Field Report

**The Park Danforth** **Project No:** 13-059-00  
**Portland ME** **Field Report No:** 9

**To:** Mark Donovan **Time of Visit:** 9:30 AM  
 PC Construction **Date of Visit:** 3/22/2016  
 131 Presumpscot Street **Weather:** Sunny, Cold 35F  
 Portland ME

**Submitted by:** Scott Timmons **Copies:**  
**Present:** Scott Timmons (LBA), Kim Ron Norton Construction Management Consultin  
 McCarthy (LBA) Andrew Pires PC Construction  
 Kemp Carey PC Construction

Item	Description	Status:
9.1	<b><u>WORK IN PROGRESS</u></b> a. Steel erection ongoing at west wing of tower through level 4 b. Steel decking installation of tower levels 3 and 4 ongoing c. Steel decking installation of tower east levels 5 and roof underway d. East wing garage slab underway e. Exterior CFMF framing levels 3 and 4 underway f. Exterior Forest Ave terrace formwork ongoing g. Level 1 interior partition framework underway h. Level 1 spray fireproofing underway	Observation
9.2	Protect installed spray-applied fireproofing in strict accordance with manufacturers instructions	Observation
9.3	<b><u>Interior Partition Deflection Head Track</u></b> Interior framing is being installed with a standard deep leg track in lieu of a slotted deflection track as submitted in Submittal 09 21 16-001	Correct Work
9.4	<b><u>Interior Framing</u></b> Interior framing is being installed on Level 1. Please submit engineered shop drawings for all new partitions with special loading conditions per Section 09 21 16-1.04.B.2	CM follow up
9.5	<b><u>Level 2 Balcony</u></b> Verify levelness of level 2 balcony floor plate/framing between 2.5 and 3 line. (Reference Photo B P2 of 6)	CM follow up

---

Item	Description	Status:
9.6	<b><u>Plumbing/Wall Conflict</u></b> There is a plumbing piping insert near Admin toilets that appears to protrude from wall framing.	Correct Work

---

**Attached Sketches:**



Tower looking south east

**A**



Tower from Arbor Street at Forest Ave.

**B**



West wing from Arbor street looking south east

**A**



Balcony steel underside from administrative offices (between grid lines 2.5 and 3)

**B**



East wing of tower from courtyard looking south east

**A**



West wing of Tower from courtyard looking North

**B**



East wing parking garage

**A**



West wing parking garage

**B**



Exterior Forest Ave terrace formwork

**A**




West wing tower north side

**B**



Level 1 administrative area interior partition

**A**



**B**