BOILER SCHEDULE

TAG	B-1	B-2	B-3
TYPE	CONDENSING	CONDENSING	CONDENSING
MANUFACTURER	WEISSMANN	WEISSMANN	WEISSMANN
BOILER MODEL	MTOCROSSAL CM2-31	MTOCROSSAL CM2-31	MTOCROSSAL CM2-31
GROSS INPUT (MBH)	1,112	1,112	1,112
GROSS OUTPUT (MBH)	1,078	1,078	1,078
NET AHRI RATING, MBH	937	937	937
COMBUSTION EFFICIENCY (%)	95.0%	95.0%	95.0%
TEMP RISE, DEG F	28.7	28.7	28.7
FLOW, GPM	75	75	75
MAX P.D.	2.0 FT	2.0 FT	2.0 FT
FLUID	WATER	WATER	WATER
MAX OPERATING PRESSURE	75 PSIG	75 PSIG	75 PSIG
SHIPPING WEIGHT (LBS)	800	800	800
WATER CONTENT, U.S. GAL.	74	74	74
OVERALL LENGTH (IN.)	73"	73"	73"
WIDTH (IN.)	36-1/2"	36-1/2"	36-1/2"
HEIGHT (IN.)	66"	66"	66"
VENT CONN. DIA (IN.)	8"	8"	8"
VENT CATEGORY	IV	IV	IV
AIR INLET CONN. (IN.)	8"	8"	8"
WATER CONN. (IN.)	2-1/2"	2-1/2"	2-1/2"
BOILER DRAIN	1"	1"	1"
CONDENSATE DRAIN	3/4"	3/4"	3/4"
FUEL	NATURAL GAS	NATURAL GAS	NATURAL GAS
GAS CONN. (IN)	1-1/4"	1-1/4"	1-1/4"
GAS PRESSURE, NATURAL	4" TO 14" WC	4" TO 14" WC	4" TO 14" WC
2-STAGE or FULL MOD.	FULL MOD - 20% - 100%	FULL MOD - 20% - 100%	FULL MOD - 20% - 100%
ELECTRICAL	120/1/60	120/1/60	120/1/60
MAX POWER CONSUMPTION	368 W	368 W	368 W

NOTES:
1. PROVIDE DIRECT PIPED COMBUSTION AIR AND COMMON VENTED FLUE.
2. BOILERS SHALL BE SUITABLE FOR ZERO GPM - NO FLOW SWITCH REQUIRED.
3. PROVIDE CONDENSATE NEUTRALIZATION KITS.

"HM" HEATING DISTRIBUTION MANIFOLDS (SEE 23 09 00)

TAG	MANIFOLD LOCATION	PIPE ROUTING TO FINTUBE	ZONE 1	ZONE 2	ZONE 3	ZONE 4	ZONE 5	ZONE 6	TOTAL
1-1	1ST FLOOR CEILING	DOWN IN WALLS	HR	STAFF	COO	FACILITY	BOARD	CORR	
GPM			1.0	1.0	1.0	1.0	1.0	1.0	6.0
1-2	1ST FLOOR CEILING	DOWN IN WALLS	FINANCE	CFO	ASSIST	CEO	APT F	APT G	
GPM			1.0	1.0	1.0	1.0	1.5	1.5	7.0
1-3	1ST FLOOR CEILING	DOWN IN WALLS	APT D	APT E	APT A	LOBBY			
GPM			1.5	1.5	1.5	1.0			5.5
1-4	1ST FLOOR CEILING	DOWN IN WALLS	APT C	APT K	APT M				
GPM			2.0	2.0	1.5				5.5
2-1	1ST FLOOR CEILING	UPFEED	APT H	APT M	APT L	SITTING	CORR		
GPM			1.5	1.5	1.5	1.5	1.5		7.5
2-2	1ST FLOOR CEILING	UPFEED	APT A	APT J	GROUP	APT F	APT G		
GPM			1.5	1.5	2.0	1.5	1.5		8.0
2-3	1ST FLOOR CEILING	UPFEED	APT D	APT E	APT A	LOBBY			
GPM			1.5	1.5	1.5	1.0			5.5
2-4	1ST FLOOR CEILING	UPFEED	APT B	APT C	SITTING	APT M			
GPM			2.0	2.0	1.0	1.5			6.5
3-1	2ND FLOOR CEILING	UPFEED	APT H	APT M	APT L	SITTING	CORR		
GPM			1.5	1.5	1.5	1.0	1.0		6.5
3-2	2ND FLOOR CEILING	UPFEED	APT A	APT J	APT F	APT G			
GPM			1.5	1.5	1.5	1.5			6.0
3-3	2ND FLOOR CEILING	UPFEED	APT D	APT E	APT A	LOBBY			
GPM			1.5	1.5	1.5	1.0			5.5
3-4	2ND FLOOR CEILING	UPFEED	APT B	APT C	SITTING	APT M			
GPM			2.0	2.0	1.0	1.5			6.5
4-1	3RD FLOOR CEILING	UPFEED	APT H	APT M	APT L	SITTING	CORR		
GPM			1.5	1.5	1.5	1.0	1.0		6.5
4-2	3RD FLOOR CEILING	UPFEED	APT A	APT J	GROUP	APT F	APT G		
GPM			1.5	1.5	2.0	1.0	1.5		7.5
4-3	3RD FLOOR CEILING	UPFEED	APT D	APT E	APT A	LOBBY			
GPM			1.5	1.5	1.5	1.0			5.5
4-4	3RD FLOOR CEILING	UPFEED	APT B	APT C	SITTING	APT M			
GPM			2.0	2.0	1.0	1.5			6.5
5-1	4TH FLOOR CEILING	UPFEED	APT H	APT M	APT L	SITTING	CORR		
GPM			1.5	1.5	1.5	1.0	1.0		6.5
5-2	4TH FLOOR CEILING	UPFEED	APT A	APT J	COMMUNITY	APT F	APT G		
GPM			1.5	1.5	2.0	1.5	1.5		8.0
5-3	4TH FLOOR CEILING	UPFEED	ELEV	APT E	APT A	LOBBY			
GPM			1.5	1.5	1.5	1.0			5.0
5-4	4TH FLOOR CEILING	UPFEED	APT B	APT C	OFFICE				
GPM			2.0	2.0	1.0				5.0
									126.5

AIR CONTROL SCHEDULE

	HEATING	DHW
SECONDARY SYSTEM		
AIR & DIRT SEPARATOR	AS-1	------
MFR-MODEL	TACO 4904AD-125	------
INLET/OUTLET	4"	------
PRESSURE DROP	2.0'	------
STRAINER	YES	------
BLADDER-TYPE EXPANSION TANK	ET-1	ET-2
MFR-MODEL	TACO CA-500-125	TACO PAX-130
SYSTEM HEIGHT, FT	60	------
STATIC PRESSURE AT TANK, PSI.	26.0	------
PSI REQ'D. AT HIGHEST TERM UNIT	5	------
TANK PRE-CHARGE PRESSURE	31.0	------
TANK DIAMETER	24"	16"
TANK HEIGHT	85.75"	52.5"
ACCEPTANCE VOLUME	132 GAL	19 GAL
ASME PRESSURE RATING	125	125

FINTUBE SCHEDULE - APARTMENTS

TAG	STERLING MODEL #	TYPE	MOUNTING HEIGHT, TOP OF ENCLOSURE	ENCLOSURE HEIGHT	DEPTH FROM WALL	No. OF TIERS	BTU / FT. WITH 1.0 GPM FLOW	AWT	EAT	ELEMENT	FIN DIMENSIONS	FINS/FT
FT-X	STERLING SYNERGY SG-500	LOW TEMP RESIDENTIAL FINTUBE	9-1/16"	9-1/16"	3-13/16"	1	567	150	70	3/4"	3-1/4" SQ.	51

TYPE	APARTMENT	APARTMENT GPM	FINNED ELEMENT LENGTHS						LOOP SIZE	BTUH		
			LIVING ROOM	BEDROOM	MBR	KITCHEN	CLOSET	TOTAL FT				
1 BR	TYPE A	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		
2 BR	TYPE B	2.0	11 FT + 6 FT	12 FT	10 FT	TH-1		39	3/4"	22,113		
1 BR - LARGE	TYPE C - 1ST	2.0	12 FT	8 FT + 8 FT			3 FT	35	3/4"	19,845		
1 BR - LARGE	TYPE C - 2, 3, 4, 5	2.0	12 FT + 2FT, 3FT + 5FT	8 FT + 8 FT			3 FT	35	3/4"	19,845		
1 BR	TYPE D	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		
1 BR	TYPE E	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		
1 BR	TYPE F	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		
1 BR	TYPE G	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		
1 BR	TYPE H	1.5	8 FT + 8 FT	12 FT		TH-1		28	3/4"	15,876		
1 BR	TYPE J	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		
2 BR	TYPE K	2.0	11 FT + 6 FT	12 FT	10 FT	TH-1		39	3/4"	22,113		
1 BR	TYPE L	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		
1 BR	TYPE M	1.5	8 FT + 8 FT	12 FT				28	3/4"	15,876		

NOTES:
1. "TH-1" IN KITCHENS - SEE 238239.
2. PROVIDE EXTENSION SETS, CORNERS, AND WALL JOINERS TO MINIMIZE FLOOR PENETRATIONS. EXTEND PIPING THROUGH THESE SECTIONS.
3. SEE HEATING DISTRIBUTION MANIFOLD SCHEDULE.

HYDRONIC PUMP SCHEDULE

TAG	SYSTEM	MFR.	MODEL	SUCT X DISCH	TYPE	PUMPED FLUID	PERFORMANCE				ELECTRICAL			ELECTRICAL COORDINATION				NOTES
							GPM	HEAD	RPM	NPSH	S/HP	NOL HP	MOTOR HP	VOLTS/PH (60 Hz.)	VFD FURN. BY	STARTER FURN. BY	BOTH PUMPS RUN?	DISC. SWITCH FURN BY	
P-1A	HEATING	TACO	SKV-30006-1760-7.5	3 X 3	INTEGRAL VARIABLE SPEED	WATER	225	65	3,600	15	5.7	7.5	7.5	208/3	INTEGRAL	------	NO, LEAD-LAG	DIV 26	1, 2
P-1B	HEATING	TACO	SKV-30006-1760-7.5	3 X 3	INTEGRAL VARIABLE SPEED	WATER	225	65	3,600	15	5.7	7.5	7.5	208/3	INTEGRAL	------	NO, LEAD-LAG	DIV 26	1, 2
P-2A	DHW	TACO	1635	1.5 x 1.5	VERTICAL	WATER	26.4	20	1,760	2	0.4	0.52	3/4	208/3	------	DIV 26	NO, LEAD-LAG	DIV 26	
P-2B	DHW	TACO	1635	1.5 x 1.5	VERTICAL	WATER	26.4	20	1,760	2	0.4	0.52	3/4	208/3	------	DIV 26	NO, LEAD-LAG	DIV 26	

NOTES:
1. PROVIDE VARIABLE FLOW MODE.
2. PROVIDE SUPPORT STAND.

UNIT HEATER SCHEDULE

TAG	SERVES	FLOOR	MFR. -MODEL	SIZE	TYPE	MBH	CFM	EAT (DEG.-F)	LAT (DEG.-F)	GPM	FLUID	EWT	LWT	MOTOR TYPE	MOTOR HP	ELECT	MAX WPD	PIPE RUNOUT SIZE	CONTROL VALVE	NOTES
CUH-1	GARDEN CONNECTION	1	TRANE FF- E-B	400	HORIZ RECESSED	22.7	294	70	141.3	1.5	WATER	160	129.6	ECM	0.13	120-1-60	4.1	3/4"	2-WAY	1
CUH-2	VESTIBULE - 145	1	TRANE FF- N-B	1200	VERTICAL INVERTED RECESSED	62.6	830	70	139.6	4.0	WATER	160	128.6	ECM	0.13 + 0.22	120-1-60	2.8	1"	2-WAY	1
CUH-3	VESTIBULE - 138	1	TRANE FF- N-B	1200	VERTICAL INVERTED RECESSED	62.6	830	70	139.6	4.0	WATER	160	128.6	ECM	0.13 + 0.22	120-1-60	2.8	1"	2-WAY	1
CUH-4	STAIR A	1	TRANE FF- E-B	400	HORIZ RECESSED	22.7	294	70	141.3	1.5	WATER	160	129.6	ECM	0.13	120-1-60	4.1	3/4"	2-WAY	1
CUH-5	STAIR B	1	TRANE FF- E-B	400	HORIZ RECESSED	22.7	294	70	141.3	1.5	WATER	160	129.6	ECM	0.13	120-1-60	4.1	3/4"	2-WAY	1
CUH-6	NEW BLDG. LOBBY 1010	1	TRANE FF- E-B	800	HORIZ RECESSED	27.8	340	70	145.3	2.0	WATER	160	132.2	ECM	0.22	120-1-60	2.1	3/4"	2-WAY	1
CUH-7	STAIR A	G	TRANE FF- F-B	800	VERT CAB FLAT-TOP	46.2	610	70	139.8	3.0	WATER	160	129.1	ECM	0.22	120-1-60	4.3	3/4"	2-WAY	1
CUH-8	STAIR B	G	TRANE FF- F-B	800	VERT CAB FLAT-TOP	46.2	610	70	139.8	3.0	WATER	160	129.1	ECM	0.22	120-1-60	4.3	3/4"	2-WAY	1
CUH-9	ELEV LOBBY A	G	TRANE FF- N-B	400	VERTICAL INVERTED RECESSED	22.7	294	70	141.3	1.5	WATER	160	129.6	ECM	0.13	120-1-60	4.1	3/4"	2-WAY	1
CUH-10	ELEV LOBBY B	G	TRANE FF- N-B	400	VERTICAL INVERTED RECESSED	22.7	294	70	141.3	1.5	WATER	160	129.6	ECM	0.13	120-1-60	4.1	3/4"	2-WAY	1
CUH-11	VESTIBULE - 1019	1	TRANE FF- N-B	1200	VERTICAL INVERTED RECESSED	62.6	830	70	139.6	4.0	WATER	160	128.6	ECM	0.13 + 0.22	120-1-60	2.8	1"	2-WAY	1
CUH-12	VESTIBULE - 1015	1	TRANE FF- N-B	1200	VERTICAL INVERTED RECESSED	62.6	830	70	139.6	4.0	WATER	160	128.6	ECM	0.13 + 0.22	120-1-60	2.8	1"	2-WAY	1
CUH-13	STAIR LOBBY B 1021	1	TRANE FF- N-B	1200	VERTICAL INVERTED RECESSED	62.6	830	70	139.6	4.0	WATER	160	128.6	ECM	0.13 + 0.22	120-1-60	2.8	1"	2-WAY	1
CUH-14	**ELEVATOR LOBBY 3003**	**3**	**TRANE FF- E-B**	**800**	**HORIZ RECESSED**	**27.8**	**340**	**70**	**145.3**	**2.0**	**WATER**	**160**	**132.2**	**ECM**	**0.22**	**120-1-60**	**2.1**	**3/4"**	**2-WAY**	**1**
UH-1	FIRE PUMP ROOM	G	TRANE UHS	36	HORIZ. UH	16.8	550	60	88.3	1.6	WATER	160	130.0	TEAO	1/15	120-1-60	0.1	3/4"	2-WAY	1
UH-2	ELECTRICAL RM	G	TRANE UHS	36	HORIZ. UH	16.8	550	60	88.3	1.6	WATER	160	130.0	TEAO	1/15	120-1-60	0.1	3/4"	2-WAY	1
UH-3	STORAGE RM G008	G	TRANE UHS	36	HORIZ. UH	16.8	550	60	88.3	1.6	WATER	160	130.0	TEAO	1/15	120-1-60	0.1	3/4"	2-WAY	1
UH-4	TRASH RM G011	G	TRANE UHS	36	HORIZ. UH	16.8	550	60	88.3	1.6	WATER	160	130.0	TEAO	1/15	120-1-60	0.1	3/4"	2-WAY	1
UH-5	GARAGE	G	TRANE UHP	500	VERTICAL UH	240.0	8,020	60	87.7	23.0	WATER	160	130.0	TEAO	1-1/2	208/3/60	2.3	2"	3-WAY	1
UH-6	GARAGE	G	TRANE UHP	500	VERTICAL UH	240.0	8,020	60	87.7	23.0	WATER	160	130.0	TEAO	1-1/2	208/3/60	2.3	2"	3-WAY	1
UH-7	GARAGE	G	TRANE UHS	360	HORIZ. UH	195.0	5,500	60	92.8	23.0	WATER	160	130.0	TEAO	1/2	208/3/60	2.1	2"	3-WAY	1
UH-8	STORAGE RM	G	TRANE UHS	36	HORIZ. UH	16.8	550	60	88.3	1.6	WATER	160	140.0	TEAO	1/15	120-1-60	0.1	3/4"	2-WAY	1
UH-9	**STORAGE 123B**	**1**	**TRANE UHS**	**18**	**HORIZ. UH**	**8.0**	**350**	**60**	**81.2**	**1.0**	**WATER**	**160**	**140.0**	**TEAO**	**16W**	**120-1-60**	**0.1**	**1/2"**	**2-WAY**	**1**
TH-1	APT. KITCHENS W/OUTSIDE WALL	ALL	BEACON MORRIS	K-84	TOE SPACE HEATER	6.3	103	70	126.6	1.0	WATER	160	147.4	ODP	0.034	120-1-60	2.0	3/4"	NONE	

NOTES:
1. POWER WIRING TO UNIT HEATER BY DIV 26. ALL LOW VOLTAGE CONTROL WIRING, THERMOSTAT, RELAYS, AND TRANFORMERS BY DIV. 23. DISCONNECT SWITCH: PROVIDE BY UNIT HEATER MANUFACTURER.

FINNED TUBE RADIATION SCHEDULE

TAG	STERLING MODEL #	TYPE	ENCLOSURE LENGTH	MOUNTING HEIGHT, TOP OF ENCLOSURE	ENCLOSURE HEIGHT	DEPTH FROM WALL	No. OF TIERS	BTU / FT	GPM	AWT	EAT	ELEMENT	FIN DIMENSIONS	FINS/FT	PIPE RUNOUT SIZE	NOTES
FT-F	JVB-FT	FRONT & TOP OUTLET, FLAT TOP - STRAIGHT	SEE PLANS	23-15/16"	20"	5-5/16""	1	860	SEE PLANS	150	70	3/4"	4-1/4 X 3-5/8	50	1/2"	
FT-R	JVB-FT	FRONT & TOP OUTLET, FLAT TOP - CUSTOM RADIUS	SEE PLANS	23-15/16"	20"	5-5/16""	1	860	SEE PLANS	150	70	3/4"	4-1/4 X 3-5/8	50	1/2"	1
FT-P	JVB-PM	PEDESTAL	SEE PLANS	10-3/4"	10-3/4"	8-1/16"	1	680	SEE PLANS	150	70	3/4"	4-1/4 X 3-5/8	50	1/2"	

NOTES
1. SEE ARCHITECTURAL PLANS FOR WALL RADIUS.
2. PROVIDE RETURNS WITHIN ENCLOSURE WHERE APPLICABLE.

BAS POINTS LIST

POINT NAME	DEVICE	AI	AO	DI	DO	FAIL POSITION	ALARM	NOTE
ENERGY RECOVERY UNITS- ERU-A, ERU-B								
START STOP	WIRE TO ERU-B CONTROLLER				X			ERU-A IS CONSTANT ON
UNIT CONTROL - FANS, WHEELS, TEMPS, ETC	FACTORY CONTROLS							UNIT HAS SELF CONTAINED DDC CONTROLS - SEE 237200
FAULT	WIRE TO ERU CONTROLLER			X			FAULT	
BISTRO HOOD MAKEUP AIR UNIT - MUA-1, EF-K								
START STOP - EF, MUA	CONTROLLER BY DIV 11							EF & MUA INTERLOCK
SPACE TEMPERATURE		X					HI & LO	
SUPPLY TEMP		X					HI & LO	
PACKAGED ROOFTOP AC - RTU-1								FACTORY DDC CONTROLS - SEE SPEC 237433, BACNET
UNIT STATUS				X			FAULT	
SPACE TEMPERATURE	WALL TEMP SENSOR	X					HI & LO	
SPACE CO2	DUCT CO2 SENSOR	X					HIGH	CO2 SENSOR FURNISHED BY 237413
SUPPLY TEMP	DUCT TEMP SENSOR	X					HI & LO	MONITORING
UNIT HEATERS, CABINET UNIT HEATERS		**AI**	**AO**	**DI**	**DO**			
SPACE TEMP	WALL TEMP SENSOR	X					HI & LO	
VALVE POSITION	2-WAY VALVE				X	OPEN		
FAN ON - OFF	UNIT HEATER FAN				X			
APARTMENT HEATING FINTUBE								STAND ALONE, NOT WIRED BAS
NO DDC								
APARTMENT DUCTLESS SPLITS								STAND ALONE, NOT WIRED BAS
NO DDC								
OTHER FINTUBE & DUCTLESS SPLIT								
SPACE TEMPERATURE		X					HI & LO	
FINTUBE VALVE POSITION	2-WAY VALVE				X	OPEN		
DUCTLESS SPLIT COOLING	DUCTLESS SPLIT				X			
HEATING PLANT	BOILER PLANT CONTROLLER (BPC)	FURNISHED WITH BOILERS (235216)						
BOILER PLANT ENABLE	BOILER CONTROL BOARD							START/STOP AT BPC, NOT BAS
HEATING PUMP ENABLE	SMART PUMP							SMART PUMP - START-STOP FROM BPC
HEATING PUMP CONTROL, LEAD/LAG	SMART PUMP							SMART PUMP CONTROL
HEATING PUMP FAULT	CURRENT SENSOR			X			FAULT	
COMMON HWS TEMP	TEMP SENSOR BY 235216							WIRE TO BPC
HEATING HWS TEMP	TEMP SENSOR BY 235216							WIRE TO BPC
HEATING HWR TEMP	TEMP SENSOR BY 235216							WIRE TO BPC
HEATING LOOP TEMP CONTROL	MIXING VALVE BY 235216							
HWS TEMP. CONTROL	BOILER CONTROL BOARD							OA RESET
HWS BYPASS VALVE	2-WAY MODULATING VALVE		X					
OUTSIDE AIR TEMPERATURE	TEMP SENSOR BY 235216							WIRE TO BPC
BOILER FAULT	BOILER CONTROL BOARD			X			FAULT	BPC FAULT OUTPUT
BOILER FLOW								BOILER FLOW SWITCH NOT NEEDED WITH SPEC'D BOILE
BOILER FIRING RATE OR SETPOINT	BOILER CONTROL BOARD							WIRE TO BPC
DHW HEATING		**AI**	**AO**	**DI**	**DO**			
DHW TANK TEMPERATURE	TANK SENSOR PROVIDED BY 223500							WIRE TO BPC
DHW TEMPERATURE, DOWNSTREAM OF TMV	TEMP SENSOR	X					HIGH	MONITOR & AL ARM
DHW PUMP ENABLE	BOILER CONTROL BOARD				X			SIGNAL FROM BPC, BAS PROVIDE AUTO LEAD-LAG
DHW PUMP FAULT	CURRENT SENSOR			X			FAIL	
DHW RECIRC PUMP ENABLE	BOILER CONTROL BOARD							WIRE TO BPC
FANS - HEAT RELIEF								
HEAT RELIEF - TEMP	WALL TEMP SENSOR	X					HI	
HEAT RELIEF - ENABLE FAN	FAN START/STOP				X			
HEAT RELIEF - INTAKE DAMPER	MOTORIZED DAMPER ACTUATOR				X			
GAS DETECTION								
CARBON MONOXIDE - BOILER ROOM	CO DETECTOR			X			MID & HIGH	
NATURAL GAS - BOILER ROOM	NAT GAS DETECTOR			X			MID & HIGH	
CARBON MONOXIDE - BISTRO	CO DETECTOR			X			MID & HIGH	
NATURAL GAS - BISTRO	NAT GAS DETECTOR			X			MID & HIGH	
GARAGE VENTILATION		**AI**	**AO**	**DI**	**DO**			
GAS DETECTION, PPM	GAS DETECTOR - SEE 230900	X					WARN, HIGH	
ALARM	GAS DETECTOR - SEE 230900			X				
INTAKE DAMPER	MOTORIZED DAMPER ACTUATOR				X			
DISCHARGE DAMPER	MOTORIZED DAMPER ACTUATOR				X			
INTAKE DAMPER PROOF	END SWITCH			X				
DISCHARGE DAMPER PROOF	END SWITCH			X				
EXH FAN START-STOP	VFD				X			
EXH FAN AIRFLOW	VFD		X					
FAN STATUS	VFD			X				
DOMESTIC WATER BOOSTER PUMP								
ALARM	PUMP ALARM CONTACT			X			FAULT	221123
FIRE PUMP DIESEL TANK								
LEAK ALARM	LEAK DETECTOR			X			FAULT	213116
ELEVATOR SUMP PUMPS								
ALARM	PUMP ALARM CONTACT			X			FAULT	221429

LAVALLEE|BRENSINGER ARCHITECTS
155 Dow Street, Suite 400, Manchester, NH 03101
92 Montvale Ave., Suite 2150, Stoneham, MA 02180
NH: 603.622.5450 MA: 718.462.7283 www.LBPA.com

Allied Engineering
Structural Mechanical Electrical Commissioning
160 Veranda Street
Portland, Maine 04103
T: 207.221.2366
F: 207.221.2366
Web: www.alliedeng.com

IAN A. MACDONALD No. 8990 LICENSED PROFESSIONAL ENGINEER STATE OF MAINE

Graphic Scale: 1" 1/2" 0 1

The Park Danforth

777 Stevens Ave, Portland, ME, 04103

NO.	DESCRIPTION	DATE
1	Addendum No. 2	2015-06-25

N

CONTENT:
MECHANICAL SCHEDULES

DRAWN BY: REW
PROJECT NO: 12-055-00
DATE: 6/5/2015
REVISED: OCTOBER 16, 2015
SCALE: AS NOTED

MH6.1

Project Phase
CONFORMANCE SET

COPYRIGHT © 2014 BY LAVALLEE|BRENSINGER PROFESSIONAL ASSOCIATION. ALL RIGHTS RESERVED. NO REPRODUCTION WITHOUT PERMISSION.

A1 MECHANICAL SCHEDULES
NONE

M:\Projects\2014\14028 - Park Danforth\05 Drawing Files\MH6.1_MECH.vwx Oct 15, 2015 - 12:07pm