NORRIS INC

PO Box 2551
2257 West Broadway
South Portland, ME 04106

1.800.370.3473
fax 207.879.0540

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/09/16

January 20, 2016

Scope of Work: Park Danforth

BH Milliken is installing new fire alarm devices for the new addition. The existing panel will be replaced with a new addressable fire alarm panel large enough to accommodate the fire alarm devices in the existing building. The main control panel will be located in the new addition in "Fire 134". There will be a remote annunciator and remote mic located in vestibule 138

This system is a voice evacuation system. There is an existing radio master box on site which will be reused. No new zones should be required.

Norris Inc. will provide the fire alarm equipment, submittal documents, fire alarm permits and final connections per City of Portland requirements.

Best Regards,

Melissa Peters
Systems Integrator
Norris Inc.
207-883-3473 x1104
melissap@norrisinc.com