E1 TYPICAL UNIT TYPE A

1/4" = 1'-0"

E4 TYPICAL UNIT TYPE B

1/4" = 1'-0"

E7 TYPICAL UNIT TYPE C

1/4" = 1'-0"

A1 TYPICAL UNIT TYPE D

1/4" = 1'-0"

A5 TYPICAL UNIT TYPE E

1/4" = 1'-0"

## APARTMENT LUMINAIRE SCHEDULE

| Type | Item | Room Name | Manufacturer | Series / Model Number | Description |
|---|---|---|---|---|---|
| CM11 | Ceiling Mount | Bathroom | Progress | P7383-30 | Contour White Acrylic Close to Ceiling Dim: 14" D x 3-5/8" 6" H Lamping: (1)-22w & (1)32w |
| CM12 | Ceiling Mount | Entrance | Progress | Maier P3675-09WB | Dim : 18" D x 6-1/4" H Fin: Satin nickel Shade : white etched acrylic bowl Lamp: GU24 (2) 26w CFL |
| CM13 | Ceiling Mount | Closets | Progress | Round White Acrylic P7378-30 | Dim: 14" D x 3-3/4" Fin: white acrylic diffuser Lamp: (3) 13w Quad or 2 pin |
| CM14 | Ceiling Mount | Kitchen Island | Winona | Giselle 5801 LED - WFG5801 18Dia LDP1A 35K MVOLT N80 FAB1:BN | Dim : 18" D x 7.5" shade Ht - 12"OAH Fin:Linen Cream Brushed Nickel Lamp: 35K LED |
| FL1 | Fluorescent | Closets | Progress | Slim Line Wrap P7137-30STR | Dim: 26-3/4" ILx 2-1/2"H x 6-1/4"D Lamp: T-8 |
| R13 | 5-1/2" LED Flush Mount | Bathroom shower | Progress | P8240-28/30K90-AC1-L06 | 5-1/2"D x 1-1/2" H Round Flushmount Frosted Acrylic Lens Cover Lumen output: one integral 12w LED module included 630 Lumens |
| R3 | 7" LED Slim Surface | Living Room | Philips Lightolier | S7R830K10 | Dim: 7" Dia installs in standard J box Lamp: LED 14 w 980 Lumen output |
| R3 ALT | 5" LED Recessed | Living Room | Progress | Trim: P8061-28-30K9-AC-L08 White Housing: P85TG | 5" LED recessed Dim: Housing - Ceiling opening 5-1/4" - Recessed Depth 7-1/2" Frosted Acrylic Lens Cover Lumen output: 800 (compares to 65 w incandescent) CRI : 70 (+) |
| UC1 | Under cabinet | Kitchen | Progress | P7013 -30 P7005-30 | Hide a Lite 120 V LED Dimmable Strips Dim: 3-1/2" w x 18" L x 1" h |
| VL1 | Vanity | Bathrooms | Progress | P27080-09 | InviteVanity Light (4 light) - Dim: 32-1/2" w x 7-3/8" h x 7-1/2" ext brush nickel finish Lamp: 4 Med base 100 w max |

REISSUE ENTIRE SHEET

1

1 SWITCH TOP HALF OF RECEPTACLE

A7 KEY NOTES


LAVALLEE|BRENSINGI

155 Dow Street, Suite 400, Mar
92 Montvale Ave., Suite 2150, S
NH: 603.622.5450 MA: 781.46


Reviewed for Code Compliance
Inspectional Services Division
Approved with Conditions
Date: 02/09/16


Allied Engineering
Structural Mechanical Electrical Commissioning

160 Veranda Street
Portland, Maine 04103
T: 207.221.2260
F: 207.221.2266
Web: www.allied-eng.com


The Park Danforth

777 Stevens Ave, Portland, ME, 04103

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | Addendum No 2 | 2015-06-25 |

CONTENT:

ENLARGED PLANS

| | |
|---|---|
| DRAWN BY: | Author |
| PROJECT NO: | - |
| DATE: | 06/05/2015 |
| REVISED: | |
| SCALE: | AS NOTED |

E4.1

Project Phase

100% CONSTRUCTION DOCUMENTS


COPYRIGHT © 2014 BY LAVALLEE/BRENSINGER PROFESSIONAL ASSOCIATION. ALL RIGHTS RESERVED. NO REPRODUCTION WITHOUT PERMISSION.



6/25/2015 2:45:03 PM N:\Projects\2014\14018 – Park Danforth\00 Drawing Files - REVIT 2015\14018E.rvt