

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT

This is to certify that
HOME FOR THE AGED

Located at
777 STEVENS AVE

PERMIT ID: 2016-00171 **ISSUE DATE:** 02/09/2016 **CBL:** 146 C005001

has permission to **For the installation of a Fire Alarm System (Notifier by Honeywell) - installation of new addressable fire alarm devices to accommodate the new, five- (5-) story addition.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ Craig Messinger

/s/ Tammy Munson

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

124 Special Needs Independent Living units, 36 Intermediate Care Units and 58 senior Independent Living Units

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2016-00171	Date Applied For: 01/26/2016	CBL: 146 C005001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: 58 Senior Independent Living Units.		Proposed Project Description: For the installation of a Fire Alarm System (Notifier by Honeywell) - installation of new addressable fire alarm devices to accommodate the new, five- (5-) story addition.		
Dept: Zoning	Status: Approved	Reviewer: Christina Stacey	Approval Date: 01/29/2016	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
Dept: Fire	Status: Approved w/Conditions	Reviewer: Craig Messenger	Approval Date: 02/09/2016	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) Fire protection systems shall be maintained. If system is to be off line over 4 hours a fire watch shall be in place. Dispatch notification required 874-8576. 2) System CO detectors shall be located on the ceiling in the same room as permanently installed fuel-burning appliances and centrally located on every habitable level and in every HVAC zone of the building per NFPA 720:5.5.5.3.1. System CO detectors shall activate an audible alarm at the detector and FACP, and send an alarm signal the remote station. It shall not trip a/the master box. 3) Manual Pull Stations are required per NFPA 101:30.3.4.2.1 at all exit doorways and within 200 feet of travel. 4) The installation shall comply Protection.with the following: City of Portland Chapter 10, Fire Prevention and NFPA 1, Fire Code (2009 edition), as amended by City Code; NFPA 101, Life Safety Code (2009 edition), as amended by City Code; City of Portland Fire Department Rules and Regulations; NFPA 72, National Fire Alarm and Signaling Code (2010 edition), as amended by Fire Department Rules and Regulations; and NFPA 70, National Electrical Code (2011 edition) as amended by the State of Maine				