3RD FLOOR PLAN

1/8" = 1-0

LEVEL 4 FRAMING PLAN

1/8"=1'-0"

NOTES:

1. INDICATES SPAN DIRECTION OF 5 1/2" NORMAL WEIGHT CONC SLAB ON 3VLI 18GA GALV COMPOSITE DECK W/6x6-W1.4xW1.4 W.W.F. (2 1/2" CONC FILL OVER 3" DECK, 5 1/2" TOTAL, 3 SPAN MIN).
2. TOP OF SLAB EL 160'-11 5/8".
3. TOP OF STEEL EL 160'-6 1/8", U.N.O. BY (±X'-X")
   FF = 10-6 (UON)
   TOS = 10-0.5 (UON)

TYPICAL HANGER
NO SCALE

1 -- All Thread Rod
1 -- Ring
1 -- Hilti Shield

PLANS PREPARED BY:
BRIAN BENOIT
NICET LEVEL 3 CERT. #075934

THESE PLANS ARE SUBJECT TO MINOR DEVIATIONS, DUE TO COORDINATION AND/OR FIELD CONDITIONS, NOT AFFECTING SCOPE OF WORK OR CODE COMPLIANCE.

SCALE 1/8"=1'-0"

SCALE 1/8"=1'-0"

N

Hampshire FIRE PROTECTION
8 NORTH WENTWORTH AVENUE LONDONDERRY, NH 03053
PH:(603) 432-8221 FAX: (603) 434-3194
WEBSITE: HAMPSHIREFIRE.COM
MASS LIC# 003841 MAINE LIC# 238
VERMONT CERTIFIED

WATER SUPPLY DATA

Static pressure	62	psi
Residual pressure	60	psi
Flow	992	gpm
Location	See Site Plan	
Elevation	+9	
Date	10-25-14	Time 10:00 AM
Information by	Portland Water Dept.	

SPRINKLERS

Total This Sheet 151 | Total This Job See Sheet 1

Symbol		Description
○	3	RELIABLE F1FR SSU (1|2"Thd 5.6K) BRASS 200° (RA1425)
◉	145	RELIABLE F1FR REC PEND (1|2"Thd 5.6K) CHROME 155° (RA1414)
◀	3	RELIABLE F3QR, DRY HSW, CHROME, 1/2", 5.6K, 155 DEG. (R5734)

Drawing Title	Sheet 7, Level 3
Contract No.	4737CNH
Drawn By	Benoit
Scale	1/8" = 1'-0"
Date	2-12-16
Approval By	Portland Fire Dept. ME SFMO

Revisions:	Date:
1	
2	
3	
4	
5	
6	
7	

Project:
The Park Danforth Expansion & Renovation
777 Stevens Ave.
Portland, ME 04103

Contract with:
PC Construction
789 Stevens Ave.
Portland, ME 04103

FIRE PROTECTION ENGINEER STAMP