CITY OF PORTLAND FIRE PREVENTION BUREAU

380 Congress Street, Portland, Maine 04101 fireprevention@portlandmaine.gov (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

May 4, 2017

Responsible Party 1:				
CONGDON F GILBERT III ETALS				
141 PROSPECT ST				
PORTLAND, ME 04103				
Location	CBL	Inspection Date		
Location 52 CANCO RD	CBL 147 C001001	Inspection Date 4/20/2017		
		-		

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 5/30/2017.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 1- 19.1.2 INSIDE STORAGE NOT ORDERLY; Persons owning or having control of any property shall not allow any combustible waste material to accumulate in any area or in any manner that creates a fire hazard to life or property. In main garage area, parts area on left of garage area, office and sprinkler room.	
NFPA 70- ARTICLE 590.6 EXT. CORD USED FOR PERMENANT WIRING; Ground-fault protection for personnel for all TEMPORARY wiring installations shall be provided to comply with 590.6 (A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment or similar activities. Extension cord and strips used near work benches on charlie wall. More outlets need to be added per electrical code.	
NFPA 70- ARTICLE 406 INSUFFICIENT ELECTRICAL RECEPTICALS; This article covers the rating, type, and installations of receptacles, cord connectors, and attachment plugs. Near work benches on charlie wall.	
NFPA 101- 9.1.2 IMPROPER WIRING, NOT TO CODE; Electrical wiring and equipment shall be in accordance with NFPA 70, unless such installations are approved existing installations, which shall be permitted to be continued in service. Proper stowage of live low voltage electrical clamps from battery conditioner.	

Violation		Proposed Date of Completion
used outdoors, in excess of th Table 6.3.1, a gas cabinet, exl	R NOT SECURED; When containers, cylinders, or tanks are the quantities specified in the column for unsprinkled areas in the hausted enclosure, or containment vessel or system shall be leaking containers, cylinders, and tanks in accordance with	
FINAL DATE OF COMPLETE	ED VIOLATION(S)	//
FIRE PREVENTION BUREAU	U RE-INSPECTION OF COMPLETED VIOLATION(S)	//_
	ht to reject or modify any proposed plan of action, and may nical capacity to complete the proposed plan. Please contactaTION	=
understand that I must conte	ions listed within the timeframes provided. If I require add act the Fire Prevention Bureau <u>prior to the deadline</u> to requals of a discretion to grant or deny.	- ·
	is my responsibility to schedule a reinspection of my prope o. My failure to schedule a reinspection shall be deemed an nedied.	
	agreement, I understand that I am liable for penalties pursules \S 1-15 and 10-25, and 30-A M.R.S. \S 4452 and may be	• •
Date	Responsible Party	
Date	Responsible Party	
SEEN AND AGREED		
Date	Fire Prevention Bureau	