4 A-213 2ND FLR RESTROOM ELEV
1/2"=1'-0" ROOM 2N005

1 A-213 2ND FLR RESTROOM ELEV
1/2"=1'-0" ROOM 2N005

TYP RESTROOM TILE WALL

5 A-213 2ND FLR RESTROOM ELEV
1/2"=1'-0" ROOM 2N005

2 A-213 2ND FLR RESTROOM ELEV
1/2"=1'-0" ROOM 2N005

3 A-213 2ND FLR RESTROOM ELEV
1/2"=1'-0" ROOM 2N005

## GENERAL CONSTRUCTION NOTES

A. EXISTING CONDITIONS ARE TAKEN FROM FIELD OBSERVATIONS AND PRI CONSTRUCTION DOCUMENTS WHEN AVAILABLE AND ARE NOT GUARAN' CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TC NO ALLOWANCE WILL BE MADE FOR ADDITIONAL COSTS DUE TO CONTRACTORS FAILURE TO VERIFY EXISTING CONDITIONS AND DIMENSI.....

B. WHEN EXISTING CONSTRUCTION WHICH IS TO REMAIN IS DAMAGED DURING THE COURSE OF CONSTRUCTION AS A RESULT OF CONTRACTORS WORK, IT SHALL BE REPAIRED AND/OR REPLACED WITH SIMILAR OR LIKE MATERIALS. SUBJECT TO ARCHITECTS APPROVAL AND WITHOUT COMPENSATION.

C. ALL WORK INDICATED ON THIS DRAWING SHALL BE DONE UNDER THE GENERAL CONSTRUCTION CONTRACT UNLESS OTHERWISE NOTED.

D. G.C. TO PROVIDE SLAB INFILL (2" MIN. V.U.F.) AS NECESSARY FOR A LEVEL FINISH OVER EXISTING STRUCTURAL CONCRETE SLAB, PATCH, PREP AND REPAIR SUB FLOORS AS NECESSARY TO RECEIVE NEW FLOORING, PROVIDE NEW FLOORING AS SCHEDULED, PROVIDE TRANSITION STRIPS, TERMINATION BARS AND/OR THRESHOLDS AT ALL CHANGES IN FLOORING MATERIALS AND/OR DOORWAYS, (METAL TERM BARS, VINYL REDUCERS, ETC...)

## KEYNOTES

| | |
|---|---|
| 1 | PROVIDE SOLID PHENOLIC TOILET PARTITION PANELS FLOOR MOUNTED, OVERHEAD BRACED, PROVIDE PRIVACY HINGE AT DOORS AND CONTINUOUS BRACKETS AT ALL PANEL AND WALL CONNECTIONS, TYPICAL |
| 2 | INSTALL DOOR, FRAME AND ASSOCIATED HARDWARE. |
| 3 | MIRROR 22"X36" |
| 4 | TOILET TISSUE DISPENSER TO BE PROVIDED - BOBRICK B-386 |
| 5 | SOAP DISPENSER TO BE PROVIDED - BOBRICK B-826.18 |
| 6 | HAND DRYER UNIT - TOTO HDR101#WH |
| 7 | PROVIDE PIPE PROTECTION |
| 8 | PROVIDE NEW ADA COMPLIANT GRAB BARS - BOBRICK 5191 |
| 9 | SHOWER SHELF, MECHANICAL FASTENED WITH SS HARDWARE TYP, BRADLEY 7510 |
| 10 | MOISTURE AND MOLD RESISTANT BENCH, USE SS HARDWARE, TYP SEE DETAIL 9/A-202 |
| 11 | TOILET TISSUE DISPENSER AND SANITARY NAPKIN DISPOSAL - AMERICAN SPECIALTIES 4813 |
| 12 | 24" x 36" ADA TILT MIRROR BY G.C. |
| 13 | PROVIDE HAND SHOWER - SPEAKMAN SIM-5480-ADA |
| 14 | PROVIDE SHOWER HEAD AND CONTROLS - SPEAKMAN SIM-5410 |
| 15 | 6" X 24" OLYMPIA FIRENZE WALL TILE |
| 16 | 12" X 12-1/2" OLYMPIA O.J.JW.GRY.BL.1RR ACCENT WALL TILE |
| 17 | SCHLUTER BULLNOSE EDGING |
| 18 | PRIME AND PAINT WALL - BENJAMIN MOORE HC-27MONTEREY WHITE |
| 19 | MOLD RESISTANT GYP CEILING AT 9'-0" A.F.F. W/ 2" X 2" CEILING TILE - OLYMPIA TILE QUEBEC |
| 20 | MOUNT HOOKS WITH STAINLESS STEEL HARDWARE, TYP, BRADLEY 912 |
| 21 | 2X2 A.C.T. CEILING AT 9'-0 A.F.F. - ARMSTRONG ULTIMA#1936 |
| 22 | 2" X 4" WALL TILE - OLYMPIA |
| 23 | COVE WALL BASE AS SCHEDULED |
| 24 | KOHLER FREEWILL SHOWER INSERT |

Inspections Division
Date: 12/09/16

LICENSED ARCHITECT WILLIAM T. HARKE No. 4170 STATE OF MAINE

| REV. | DESCRIPTION | DATE | BY | CK | APP |
|---|---|---|---|---|---|
| 1-0A | FOR PERMIT | 10.31.16 | | | |
| 0-0A | FOR FINAL REVIEW | 10.14.16 | | | |

OWNER ENGINEER:
DRAWING PREPARED BY: LABELLA Associates, D.P.C.
APPROVAL STAMP:
ACCEPTED BY OE:
PE Stamp

CMP ENGINEERING
CONFIDENTIAL, PROPRIETARY and TRADE SECRET INFORMATION
Property of CENTRAL MAINE POWER CO.
CENTRAL MAINE POWER

| REV. | DATE | BY | DESCRIPTION | APP. |
|---|---|---|---|---|
| 1-0A | 10-31-2016 | WTH | FOR PERMIT | |

PORTLAND SERVICE CENTER
WOMEN'S RESTROOM ELEVATIONS
SHEET 11 OF 14
PORTLAND - 162 CANCO ROAD MAINE

DR. WTH & JME | SCALE: 1/2"=1'-0" | FILE: A212 RESTROOM ELEVATIONS.DWG
CK. LABELLA | NO. A-213 | REV. 0-0A
APP. --
DATE: --

ARCH D CADD Drawing. DO NOT REVISE MANUALLY.