Inspections Division
Date: 12/09/16

TYP RESTROOM TILE WALL
2"=1'-0"

1 A204 2ND FLR PUBLIC RESTROOM ELEV
1/2"=1'-0"
ROOM 2N007

2 A204 2ND FLR PUBLIC RESTROOM ELEV
1/2"=1'-0"
ROOM 2N007

3 A204 2ND FLR PUBLIC RESTROOM ELEV
1/2"=1'-0"
ROOM 2N007

GENERAL CONSTRUCTION NOTES

A. EXISTING CONDITIONS ARE TAKEN FROM FIELD OBSERVATIONS AND PRI CONSTRUCTION DOCUMENTS WHEN AVAILABLE AND ARE NOT GUARAN' CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TC NO ALLOWANCE WILL BE MADE FOR ADDITIONAL COSTS DUE TO CONTRACTORS FAILURE TO VERIFY EXISTING CONDITIONS AND DIMENSI.....

B. WHEN EXISTING CONSTRUCTION WHICH IS TO REMAIN IS DAMAGED DURING THE COURSE OF CONSTRUCTION AS A RESULT OF CONTRACTORS WORK, IT SHALL BE REPAIRED AND/OR REPLACED WITH SIMILAR OR LIKE MATERIALS. SUBJECT TO ARCHITECTS APPROVAL AND WITHOUT COMPENSATION.

C. ALL WORK INDICATED ON THIS DRAWING SHALL BE DONE UNDER THE GENERAL CONSTRUCTION CONTRACT UNLESS OTHERWISE NOTED.

D. G.C. TO PROVIDE SLAB INFILL (2" MIN. V.I.F.) AS NECESSARY FOR A LEVEL FINISH OVER EXISTING STRUCTURAL CONCRETE SLAB, PATCH, PREP AND REPAIR SUB FLOORS AS NECESSARY TO RECEIVE NEW FLOORING, PROVIDE NEW FLOORING AS SCHEDULED, PROVIDE TRANSITION STRIPS, TERMINATION BARS AND/OR THRESHOLDS AT ALL CHANGES IN FLOORING MATERIALS AND/OR DOORWAYS. (METAL TERM BARS, VINYL REDUCERS, ETC...)

KEYNOTES

1. PROVIDE SOLID PHENOLIC TOILET PARTITION PANELS FLOOR MOUNTED, OVERHEAD BRACED, PROVIDE PRIVACY HINGE AT DOORS AND CONTINUOUS BRACKETS AT ALL PANEL AND WALL CONNECTIONS, TYPICAL
2. INSTALL DOOR, FRAME AND ASSOCIATED HARDWARE.
3. MIRROR 22"X36"
4. TOILET TISSUE DISPENSER TO BE PROVIDED - BOBRICK B-386
5. SOAP DISPENSER TO BE PROVIDED - BOBRICK B-826.18
6. HAND DRYER UNIT - TOTO HDR101#WH
7. PROVIDE PIPE PROTECTION
8. PROVIDE NEW ADA COMPLIANT GRAB BARS - BOBRICK 5191
9. SHOWER SHELF, MECHANICAL FASTENED WITH SS HARDWARE TYP, BRADLEY 7510
10. MOISTURE AND MOLD RESISTANT BENCH, USE SS HARDWARE, TYP SEE DETAIL 9/A-202
11. TOILET TISSUE DISPENSER AND SANITARY NAPKIN DISPOSAL - AMERICAN SPECIALTIES 4813
12. 24" x 36" ADA TILT MIRROR BY G.C.
13. PROVIDE HAND SHOWER - SPEAKMAN SIM-5480-ADA
14. PROVIDE SHOWER HEAD AND CONTROLS - SPEAKMAN SIM-5410
15. 6" X 24" OLYMPIA FIRENZE WALL TILE
16. 12" X 12-1/2" OLYMPIA O.J.JW.GRY.BL.1RR ACCENT WALL TILE
17. SCHLUTER BULLNOSE EDGING
18. PRIME AND PAINT WALL - BENJAMIN MOORE HC-27MONTEREY WHITE
19. MOLD RESISTANT GYP CEILING AT 9'-0" A.F.F. W/ 2" X 2" CEILING TILE - OLYMPIA TILE QUEBEC
20. MOUNT HOOKS WITH STAINLESS STEEL HARDWARE, TYP, BRADLEY 912
21. 2X2 A.C.T. CEILING AT 9'-0 A.F.F. - ARMSTRONG ULTIMA#1936
22. 2" X 4" WALL TILE - OLYMPIA
23. COVE WALL BASE AS SCHEDULED
24. KOHLER FREEWILL SHOWER INSERT

LICENSED ARCHITECT
WILLIAM T. HARKE
No. 4170
STATE OF MAINE

REV.	DESCRIPTION	DATE	BY	CK	APP
1-0A	FOR PERMIT	10.31.16			
0-0A	FOR FINAL REVIEW	10.14.16			

OWNER ENGINEER:

APPROVAL STAMP:

PE Stamp

DRAWING PREPARED BY:
LABELLA Associates, P.C.

ACCEPTED BY OE:

CMP ENGINEERING
CONFIDENTIAL, PROPRIETARY and TRADE SECRET INFORMATION
Property of CENTRAL MAINE POWER CO.

CENTRAL MAINE POWER

REV.	DATE	BY	DESCRIPTION	APP.
1-0A	10-31-2016	WTH	FOR PERMIT	

PORTLAND SERVICE CENTER
PUBLIC RESTROOM ELEVATIONS

SHEET 12 OF 14

PORTLAND - 162 CANCO ROAD MAINE

DR.	WTH & JME	SCALE: 1/2"=1'-0"	FILE: A232 RESTROOM ELEVATIONS.DWG
CK.	LABELLA	NO.	A-223
APP.	–		
DATE	–		

REV. 0-0A

ARCH D CADD Drawing, DO NOT REVISE MANUALLY.