



- ① REMOVE EXISTING BATHROOM COMPLETE. PATCH SLAB AND FINISHES AS REQUIRED.
- ② REMOVE EXISTING DOOR AND FRAME AND INFILL OPENING.
- ③ REMOVE EXISTING DOOR AND FRAME AND ENLARGE TO 36" CLEAR WIDTH FINISHED OPENING
- ④ NEW 36" DOOR IN EXISTING WALL.
- ⑤ NEW FULL HEIGHT SHELVING
- ⑥ NEW COUNTERTOP WITH BASE CABINET AND OVERHEAD CABINETS
- ⑦ NEW 36" WIDE FINISH OPENING IN EXISTING WALL.
- ⑧ EXTEND PARTITION AND INSTALL COUNTERTOP WITH BASE CABINETS
- ⑨ NEW COUNTERTOP WORK SURFACE W/ SHELVING AT ENDS AS SHOWN
- ⑩ NEW JANITOR CLOSET W/ MOP SINK
- ⑪ REMOVE EXISTING DOOR AND FRAME AND PORTION OF WALL. PATCH FINISHES.
- ⑫ REMOVE EXISTING DOORS. INSTALL TRANSACTION COUNTERTOP WITH STUD WALL BELOW AND SLIDING GLASS PANELS AT TOP.
- ⑬ REMOVE EXISTING DOOR. KEEP FRAME IN PLACE.
- ⑭ NEW DOOR & FRAME IN EXISTING OPENING
- ⑮ NEW 1 HOUR RATED PARTITION W/ 45 MIN. DOORS/FRAMES
- ⑯ CONCRETE JERSEY BARRIERS
- ⑰ NEW TOILETS /SHOWERS/DRESSING ROOMS - SEE ENLARGED PLANS
- ⑱ NEW KITCHEN COUNTERTOPS WITH BASE & OVERHEAD CABINETS AND APPLIANCES.
- ⑲ NEW 18"x18" X 60" LOCKERS AND BENCHES

LAYOUT PLAN
Scale: 3/32" = 1'-0"

CITY OF
PORTLAND
DEPT. OF
PUBLIC WORKS

INTERIOR
RENOVATIONS

Canco Road
Portland, Maine

REVISIONS

PERMIT DOCUMENTS
FEBRUARY 25, 2016

LAYOUT PLAN

Scale: As Noted