

- (b) T-8 or smaller diameter linear fluorescent
- (c) 40 lumens per watt for lamp wattage <= 15
- (d) 50 lumens per watt for lamp wattage > 15 and <= 40
- (e) 60 lumens per watt for lamp wattage > 40

Other Requirements:

- Snow- and ice-melting systems with energy supplied from the service to a building shall include automatic controls capable of shutting off the system when a) the pavement temperature is above 50 degrees F, b) no precipitation is falling, and c) the outdoor temperature is above 40 degrees F (a manual shutoff control is also permitted to satisfy requirement 'c').

Certificate:

- A permanent certificate is provided on or in the electrical distribution panel listing the predominant insulation R-values; window U-factors; type and efficiency of space-conditioning and water heating equipment. The certificate does not cover or obstruct the visibility of the circuit directory/label, service disconnect label or other required labels.

NOTES TO FIELD: (Building Department Use Only)
