Inspections Division
Date: 06/23/14

ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALL NORTH MATERIAL	WALL NORTH FINISH	WALL EAST MATERIAL	WALL EAST FINISH	WALL SOUTH MATERIAL	WALL SOUTH FINISH	WALL WEST MATERIAL	WALL WEST FINISH	CEILING MATERIAL	CEILING HEIGHT	NOTES
101	ENTRY VESTIBULE	WOM	VB	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
102	LOBBY	WD/ CPT-A	WB	PT		PT		PT		PT		SAT	18'-0"±	B
102 A	CLOSET	WD/ CPT-A	WB	PT		PT		PT		PT		EXIST	7'-10"±	
103	STAIR	CPT - C	VB	PT		PT		PT		PT		EXIST	VARIES	
104	CONFERENCE ROOM	CPT - A	EXIST	PT		PT		PT		PT		EXIST	7'-10"±	C
105	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
106	OFFICE (2)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	D
107	HALL	CPT - A/ WOM	VB	PT		PT		PT		PT		EXIST	7'-10"±	E
107 A	CLOSET	EXIST	EXIST	PT		PT		PT		PT		EXIST	7'-10"±	
108	UTILITY CLOSET	EXIST	EXIST	PT		PT		PT		PT		EXIST	7'-10"±	F
109	BATH	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	G
110	BATH	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	G
111	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
112	OFFICE (2)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
113	MAIL/ SUPPLY	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
114	CLOSET	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
115	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
116	OFFICE (2)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
117	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
118	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
119	STAIR	EXIST	EXIST	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST	7'-10"±	
120	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT			7'-10"±	
121	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
122	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
123	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
124	HALL	CPT - A	VB	PT		PT		PT		PT		SAT	7'-10"±	A
125	AFO STORAGE	VT	VB	PT		PT		PT		PT		SAT	7'-10"±	
126	BRI STORAGE	VT	VB	PT		PT		PT		PT		SAT	7'-10"±	
127	SERVER ROOM	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	
128	OFFICE (4)	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	A
129	OFFICE	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	A
130	MUSEUM	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	A
131	STORAGE	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	A
132	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	A
133	BATH	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	
134	STAIR/ ELEV. LOBBY	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
135	STAIR	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
136	ELEV. MECH ROOM	EXIST	EXIST	PT		PT		PT		PT		EXIST	7'-10"±	
137	CLOSET	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
138	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
139	BATH	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	
140	LOUNGE	VT	VB	PT		PT		PT		PT		SAT	7'-10"±	H
141	KITCHEN	VT	VB-	PT		PT		PT		PT		SAT	7'-10"±	
142	STAIR	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
143	HVAC/ BOILER	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
144	HVAC/ BOILER	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
145	ENTRY VESTIBULE	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
146	STAIR	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
147	HALL	VT	VB	PT		PT		PT		PT		EXIST	8'-6"±	
147A	EQUIP/ CYLINDERS	VT	VB	PT		PT		PT		PT		EXIST	8'-6"±	
148	WET LAB	VT	VB	PT		PT		PT		PT		EXIST	8'-6"±	
149	STORAGE	VT	VB	PT		PT		PT		PT		EXIST	8'-6"±	
150	B&L II	VT	VB	PT		PT		PT		PT		EXIST	8'-6"±	
151	BATH	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	
152	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
153	OFFICE (2)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	

ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALL NORTH MATERIAL	WALL NORTH FINISH	WALL EAST MATERIAL	WALL EAST FINISH	WALL SOUTH MATERIAL	WALL SOUTH FINISH	WALL WEST MATERIAL	WALL WEST FINISH	CEILING MATERIAL	CEILING HEIGHT	NOTES
154	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
155	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
156	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
157	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
158	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
159	OFFICE (2)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
160	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
161	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
201	STAIR	EXIST	EXIST	EXIST		EXIST		EXIST		EXIST		EXIST	7'-10"±	
202	HALL	CPT - A	VB	PT		PT		PT		PT		SAT	7'-10"±	
203	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
204	OFFICE (2)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
205	DAVE EVERS	CPT - B	VB	PT		PT		PT		PT		SAT	7'-10"±	
206	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
207	KITCHETTE	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	
208	HALL	CPT - A	VB	PT		PT		PT				EXIST	7'-10"±	
209	BATH	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	
210	BATH	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	
211	OFFICE (3 OR 4)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
212	I.T. CLOSET	CPT - A	VB	PT		PT		PT				EXIST	7'-10"±	
213	CLOSET	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	
214	OFFICE (1)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
215	OFFICE (2)	CPT - B	VB	PT		PT		PT		PT		EXIST	7'-10"±	
216	OFFICE (2)	CPT - B	VB	PT		PT		PT				EXIST	7'-10"±	A
217	OFFICE (3)	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	A

ALTERNATE ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALL NORTH MATERIAL	WALL NORTH FINISH	WALL EAST MATERIAL	WALL EAST FINISH	WALL SOUTH MATERIAL	WALL SOUTH FINISH	WALL WEST MATERIAL	WALL WEST FINISH	CEILING MATERIAL	CEILING HEIGHT	NOTES
124	HALL	CPT - A	VB	PT		PT		PT		PT		SAT	7'-10"±	
128	OFFICE (4)	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	AA, AB
130	MUSEUM	VT	VB	PT		PT		PT		PT		EXIST	7'-10"±	AB,
132	HALL	CPT - A	VB	PT		PT		PT		PT		EXIST	7'-10"±	AB,
140	LOUNGE	VT	VB	PT		PT		PT		PT		SAT	7'-10"±	AB,
141	KITCHEN	VT	VB-	PT		PT		PT		PT		SAT	7'-10"±	AB,
216	OFFICE (5)	CPT - B	VB	PT		PT		PT				EXIST	7'-10"±	AB,

MATERIALS KEY

FLOORING	
DESIGNATION	DESCRIPTION
WOM	NRF ROLL GOODS DEFENDER MATTING COLOR: COCOA 30411
CPT-A	TANDUS RIVER'S EDGE 03936 GOLDOREST 0813 MODULAR 18.125"X36.36"
CPT-B	TANDUS TRIBUTARY 03937 GOLDCREST 0813 MODULAR
CPT-C	TANDUS TRIBUTARY 03937 GOLDCREST 0813 POWERBOND 6'
WD	PLANCHERS ANCESTRAL FLOORING WHITE ASH TOSCANE FINISH
VT	JOHNSONITE FREEDOM TILE COLOR: 4113 METASTONE ALCHEMY

WALLS	
DESIGNATION	DESCRIPTION
PT-1	SHERMAN WILLIAMS - 6172
PT-2	SHERMAN WILLIAMS - 7534
PT-3	SHERMAN WILLIAMS - 6365
PT-4	SHERMAN WILLIAMS - 6544
PT-5	SHERMAN WILLIAMS - 6340

WALL BASE	
DESIGNATION	DESCRIPTION
VB	JOHNSONITE 4" WALL BASE #281 GRIZZLY
WB	STAINED TO COORDINATE WITH NEW ANCESTRAL FLOORING

FINISH NOTES

GENERAL NOTES:
- ALL METAL DOOR TRIM TO BE PT-1
-

KEYED NOTES:

A. AFFECTED BY ALTERNATE - SEE ALTERNATE FLOOR PLAN & SCHEDULE

B. NEW WOOD BASE, REMOVE OAK TRIM, PATCH & REPAIR VINYL WALL COVERING PAINT

C. ALL WOOD BASE TO REMAIN, VINYL WALL COVERING TO BE PAINTED

D. PATCH & REPAIR WALLS AT KITCHEN AREA, PAINT AS REQUIRED

E. WALK-OFF-MAT AT ENTRANCE, SEE FLOOR PLAN

F. EXISTING OR ADJACENT FINISH, GENERAL CONTRACTOR TO DECIDE

G. VINYL WALL COVERING TO BE PAINTED, NEW FIXTURES / LIGHTING BY OWNER, REMOVE GRAB BARS

PORT ▪ CITY ARCHITECTURE
65 NEWBURY STREET
PORTLAND, ME 04101
207.761.9000

REGISTERED ARCHITECT ANDREW C. MYLAND #2037 STATE OF MAINE
6.6.14

CALLAHAN
H.E. CALLAHAN CONSTRUCTION CO.

- PERMIT SET -

Biodiversity
Portland,
Maine

#	DATE	DESCRIPTION
-	-	-
-	-	-
-	-	-

Date Issued	06-06-2014
Project Number	14107
Drawing Scale	AS NOTED

ROOM FINISH SCHEDULE

Drawn By
Checked By
ACH, LAS

A3.1

COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of PORT CITY ARCHITECTURE PA