Inspections Division
Date: 12/22/16

ROOM FINISH SCHEDULE

NUM	NAME	FLOOR	BASE	WALLS (DIRECTION REFERS TO 'PLAN' NORTH) N	FINISH	E	FINISH	S	FINISH	W	FINISH	CEILING MATERIAL	FINISH	HEIGHT	NOTES
100	RECEPTION	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
101	STORAGE	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
102	X BATHROOM	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
103	STORAGE	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	SAT		X	AB
104	BREAKROOM	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
105	OFFICE	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
106	OFFICE	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
107	OFFICE	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
108	OFFICE	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
109	STAIRCASE	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
110	EMPLOYEE BREAKRM	X	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	X		X	A
111	OPEN WORKSPACE	LVT	VB	GWB	PT-1	GWB	PT-1	GWB	PT-1	GWB	PT-1	SAT		X	AB

NOTES: A. PATCH & PAINT ALL HOLES, REFINISH ALL WALLS WHERE APPLICABLE
B. MATCH SAT CEILING HEIGHT TO EXISTING CEILING HEIGHT
C.
D.

DOOR SCHEDULE

NUM	DESCRIPTION	SIZE	DOOR MAT	DOOR TYPE	DOOR RATING	FRAME MAT	NOTES
101A	STORAGE TO RECEPTION	3'-0" X 6'-8"	WD.	N/A	N/A	WD.	1
103A	STORAGE TO RECEPTION	3'-0" X 6'-8"	WD.	N/A	N/A	WD.	1
104A	OPEN WORKSPACE TO BREAKROOM	3'-0" X 6'-8"	WD.	N/A	N/A	WD.	1
105A	OPEN WORKSPACE AREA TO OFFICE	3'-0" X 6'-8"	WD.	N/A	N/A	WD.	1

NOTES: 1. REUSE SALVAGED DOORS W/ CORRECT SWINGS

PORT ▪ CITY
ARCHITECTURE

65 NEWBURY STREET
PORTLAND, ME 04101
207.761.9000

REGISTERED ARCHITECT
ANDREW C. HYLAND
#2037
STATE OF MAINE

PERMIT SET
-NOT FOR CONSTRUCTION-

Biodiversity
Portland,
Maine

#	DATE	DESCRIPTION
-	-	-
-	-	-
-	-	-

Date Issued	10-7-2016
Project Number	16114
Drawing Scale	AS NOTED

SCHEDULES

Drawn By: CR
Checked By: ACH

A5.1

COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of PORT CITY ARCHITECTURE PA