

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND

# BUILDING PERMIT

This is to certify that  
SPRINKLER SYSTEMS, INC.  
PO BOX 1285  
LEWISTON, ME 04243

For installation at  
24 TORREY ST  
SINGLE-FAMILY HOME


Job ID: 2012-01-3084-FAFS

CBL: 156- C-004-001

has permission install to install an NFPA 13D sprinkler system  
provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be

  
Fire Prevention Officer

(58)

Code Enforcement Officer / Plan Reviewer

THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
PENALTY FOR REMOVING THIS CARD

## BUILDING PERMIT INSPECTION PROCEDURES

Please call 874-8703 or 874-8693 (ONLY)

or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**

### **Final Fire**

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.



# PORTLAND MAINE

*Strengthening a Remarkable City, Building a Community for Life • [www.portlandmaine.gov](http://www.portlandmaine.gov)*

Director of Planning and Urban Development  
Penny St. Louis

**Job ID: 2012-01-3084-FAFS**  
**install an NFPA 13D sprinkler system**

**For installation at:**  
**24 TORREY ST**  
**SINGLE-FAMILY HOME**

**CBL: 156- C-004-001**

## **Conditions of Approval:**

### **Fire**

The sprinkler system shall be installed in accordance with NFPA 13D. A compliance letter is required. All control valves shall be supervised in accordance with NFPA 13D. Pad locks shall only be installed on valves designed to be secured in the open position by pad lock.



R-3 new single family  
2011-07-1749

2012 01 3084

60



# Water-Based Fire Suppression System Permit

If you or the property owner owes real estate or property taxes or user charges on any property within the city, payment arrangements must be made before permits of any kind are accepted.

Installation address: 23 Bay Street / 24 Tower CBL: 156 (004)

Exact location: (within structure) Entire

Type of occupancy(s) (NFPA & ICC): Residential - Single family dwelling

Building owner: Angus King III

Managing Supervisor (RMS): Scott E. Garland License No: 278

Supervisor phone: 207-775-1521 E-mail: scottg@sprinklersystemsinc.com

Installing contractor: Sprinkler Systems Inc. License No: 093

Contractor phone: 207-782-0104 E-mail: \_\_\_\_\_

The suppression work to be done will be: New:  Renovation:  Addition to existing system:

This is an amendment to an existing permit: Yes:  NO:  Permit no: \_\_\_\_\_

NFPA Standard this system is designed to: NFPA #13-D Edition: 2007

\*Non-NFPA systems are not approved for use within the City of Portland.

Download a new copy of this document from [www.portlandmaine.gov/fire](http://www.portlandmaine.gov/fire) for every submittal. Attach all working documents and complete approved submittals as may be required by the State Fire Marshal's Office on electronic PDF's in addition to full sized plans.

Contractor shall verify location and type of all FDCs shall be approved in writing by the Fire Prevention Bureau.

<b>COST OF WORK:</b> <u>\$2,000.00</u>
<b>PERMIT FEE:</b> <u>\$40.00</u>
(\$10 PER \$1,000 + \$30 FOR THE FIRST \$1,000)

Submit all information to the Building Inspections Department, 389 Congress Street, Room 315, Portland, Maine 04101.

Prior to acceptance of any fire protection system, a complete commissioning and acceptance test must be coordinated with all fire system contractors and the Fire Department, and proper documentation of such test(s) provided.

All installation(s) must comply with NFPA and the Fire Department Technical Standard(s).

Applicant signature: \_\_\_\_\_ Date: 1-10-2012

RECEIVED

JAN 11 2012

Dept. of Building Inspections  
City of Portland Maine

# Sprinkler Systems, Inc.

P.O. Box 1285

Lewiston, ME 04243-1285

# Letter of Transmittal

DATE	12-9-11	JOB #	11083
ATTENTION:	INSPECTIONS		
RE:	KINE RESIDENCE 23 BOY STREET PORTLAND, ME		

TO: CITY OF PORTLAND  
INSPECTIONS RM 315  
390 LEWIS ST.  
PORTLAND, ME 04101

**WE ARE SENDING YOU:**

- Attached       Under separate cover via \_\_\_\_\_ the following items:  
 Shop drawings     Prints       Plans       Samples       Specifications     Wavier or Liens  
 Copy of letter     Change order     Signed Contracts     See Below

COPIES	DATE	NO.	DESCRIPTION
1c	12-9-11	1361	SPEINKER SHOP DRAWING
1c	12-9-11	1363	HYDRAULIC CALCULATIONS PACKAGE
1c	12-16-11	9790	STATE OF MAINE SPEINKER PERMIT
1c	1-10-12	-	PORTLAND PERMIT APPLICATION
1c	11-30-11	-	FLOW TEST MAP
1c	11-4-12	2640	\$ 40.00 PORTLAND PERMIT CHECK
1c	12-9-11	1361	11217 SPEINKER DRAW

**THESE ARE TRANSMITTED as checked below:**

- For your approval       Approved as submitted       Resubmit \_\_\_\_\_ copies for approval  
 For your use       Approved as noted       Submit \_\_\_\_\_ copies for distribution

**REMARKS:**

PLANS & CALLS HAVE BEEN SUBMITTED TO STATE FIRE MARSHAL & CITY OF PORTLAND FOR APPROVALS / PERMITS

Thank You,  
SWEET E. GARLAND SET, PMS

SIGNED: \_\_\_\_\_

PMS. M.L.



**State of Maine**  
**Department of Public Safety**  
**Fire Sprinkler System Permit**



# 9790

**King Residence**

Located at: 23 Bay Street  
 In the Town of: Portland  
 Occupancy/Use: Single Family Residence  
 Type of System: NFPA 13D

Permission is hereby given to:

**Sprinkler Systems, Inc.**

PO Box 1285  
 Lewiston, ME 042431285  
 Contractor License # 93

to begin installation according to plans submittal approved by the Office of State Fire Marshal. The submittal is filed under log # **2111454**, and no departure from the application submittal shall be made without prior approval in writing. This permit is issued under the provisions of Title 32, Chapter 20, Section 12004-I. Nothing herein shall excuse the holder of this permit from failure to comply with local ordinances, zoning laws, or other pertinent legal restrictions. This permit shall be displayed at the construction site or be made readily available.

This permit was issued on **12/16/2011** for a fee paid of **\$25.00**

*This permit will expire at midnight on **Wednesday, June 13, 2012***

The expiration date applies only if the installation has not begun by that date and no permission has been granted to extend the date. Once installation begins, then the permit is valid for however long it takes to complete the installation, assuming that the work is fairly continuous.

John E. Morris  
 Commissioner

*The type of Fire Department Connection and its location is to be according to the Local Fire Department*

Within 30 days of the completion of a new fire sprinkler system or an addition to an existing fire sprinkler system, a fire sprinkler system contractor shall provide to the Office of State Fire Marshal a copy of this permit signed and dated by the certified Responsible Managing Supervisor representing that the fire sprinkler system has been installed according to specifications of the approved plan to the best of the supervisor's knowledge, information, and belief. This requirement is part of the sprinkler law, and neglect of this duty is grounds to not renew the contractor's license to do work in the State of Maine. All renewed sprinkler licenses are good for two years and expire on a June 30th.

Job completed, tested and verified by date of \_\_\_\_\_

RMS for this job: Garland Scott E.

RMS Signature: \_\_\_\_\_



**CITY OF PORTLAND, MAINE**  
 Department of Building Inspections

**Original Receipt**

Jan 11 2012

Received from 27640

Location of Work 27 Torrey St / 93 Bay St

Cost of Construction \$ \_\_\_\_\_ Building Fee: \_\_\_\_\_

Permit Fee \$ \_\_\_\_\_ Site Fee: \_\_\_\_\_

Certificate of Occupancy Fee: \_\_\_\_\_

Total: \_\_\_\_\_

Building (1L)  Plumbing (15) \_\_\_\_\_ Electrical (12) \_\_\_\_\_ Site Plan (U2) \_\_\_\_\_

Other Plumbing repair

CBL: 156 0004

Check #: 27640 Total Collected \$ 40.00

**No work is to be started until permit issued.  
 Please keep original receipt for your records.**

Taken by: [Signature]

WHITE - Applicant's Copy  
 YELLOW - Office Copy  
 PINK - Permit Copy





... Fire Protection by Computer Design

Sprinkler Systems, Inc.  
2-4 Avon Street  
P.O. Box 1285  
Lewiston, Maine 04240  
207-782-0104

Job Name : KING RESIDENCE  
Building :  
Location : 23 BAY STREET, PORTLAND, MAINE 04103  
System : 1 OF 1  
Contract : 11083  
Data File : KINGRES111083.wxf

# Fittings Used Summary

Sprinkler Systems, Inc.  
KING RESIDENCE

Page 3  
Date 12-9-2011

Fitting Legend		1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24
Abbrev.	Name																				
E	90' Standard Elbow	2	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
T	90' Flow Thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121
Z	Generic Flow Switch	2	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61


## Units Summary

Diameter Units           Inches  
Length Units             Feet  
Flow Units                US Gallons per Minute  
Pressure Units           Pounds per Square Inch

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	***** Notes *****
TYP	13.00	1.101	1T 9.563	0.500	7.039		K Factor = 4.90
to		150	0.0	9.562	0.0		
DROP	13.0	0.0306	0.0	10.062	0.308		Vel = 4.38
	0.0						
	13.00				7.347		K Factor = 4.80
1	13.00	1.101	0.0	5.000	7.347		K Factor @ node DROP
to		150	0.0	0.0	0.0		
2	13.0	0.0308	0.0	5.000	0.154		Vel = 4.38
2	13.13	1.101	1T 9.563	4.000	7.501		K Factor @ node DROP
to		150	0.0	9.562	0.0		
A	26.13	0.1116	0.0	13.562	1.513		Vel = 8.81
A	0.0	1.101	1E 3.825	14.250	9.014		
to		150	1T 9.563	13.387	4.620		
B	26.13	0.1116	0.0	27.637	3.085		Vel = 8.81
B	0.0	1.101	1T 9.563	8.083	16.719		
to		150	0.0	9.562	0.0		
C	26.13	0.1116	0.0	17.645	1.969		Vel = 8.81
C	0.0	1.101	1E 3.825	24.250	18.688		
to		150	1T 9.563	13.387	0.0		
D	26.13	0.1116	0.0	37.637	4.201		Vel = 8.81
D	0.0	1.101	1E 3.825	20.583	22.889		
to		150	0.0	3.825	0.0		
E	26.13	0.1116	0.0	24.408	2.725		Vel = 8.81
E	0.0	1.101	1E 3.825	1.417	25.614		
to		150	0.0	3.825	0.0		
RT	26.13	0.1116	0.0	5.242	0.585		Vel = 8.81
RT	0.0	1.38	1Z 3.0	8.500	26.199		
to		120	0.0	3.000	8.681		* Fixed loss = 5
RB	26.13	0.0562	0.0	11.500	0.646		Vel = 5.60
RB	0.0	1.314	1E 2.247	80.000	35.526		
to		150	1T 4.495	6.742	0.0		
X	26.13	0.0472	0.0	86.742	4.091		Vel = 6.18
X	0.0	6.16	1T 43.037	360.000	39.617		
to		140	0.0	43.037	0.0		
X1	26.13	0.0	0.0	403.037	0.012		Vel = 0.28
X1	0.0	12.34	1T 93.767	390.000	39.629		
to		140	0.0	93.767	0.0		
X2	26.13	0.0	0.0	483.767	0.001		Vel = 0.07
X2	0.0	6.16	0.0	30.000	39.630		
to		140	0.0	0.0	0.433		
TEST	26.13	0.0	0.0	30.000	0.001		Vel = 0.28
	0.0						

City Water Supply:  
 C1 - Static Pressure : 92  
 C2 - Residual Pressure: 89  
 C2 - Residual Flow : 1433

Demand:  
 D1 - Elevation : 8.734  
 D2 - System Flow : 26.1349  
 D2 - System Pressure : 40.064  
 Hose ( Adj City ) : \_\_\_\_\_  
 Hose ( Demand ) : \_\_\_\_\_  
 D3 - System Demand : 26.1349  
 Safety Margin : 51.935



HYDRAULIC DESIGN INFORMATION SHEET

Name - KING RESIDENCE Date - 12-9-2011  
Location - 23 BAY STREET, PORTLAND, MAINE 04103  
Building - System No. - 1 OF 1  
Contractor - REDFERN PROPERTIES Contract No. - 11083  
Calculated By - SCOTT E. GARLAND Drawing No. - 1 OF 1  
Construction: (X) Combustible ( ) Non-Combustible Ceiling Height 7-6  
OCCUPANCY - RESIDENTIAL - SINGLE FAMILY DWELLING

S Type of Calculation: ( )NFPA 13 Residential ( )NFPA 13R (X)NFPA 13D  
Y Number of Sprinklers Flowing: ( )1 (X)2 ( )4 ( )  
S ( )Other  
T ( )Specific Ruling Made by Date  
E  
M Listed Flow at Start Point - 20.0 Gpm System Type  
Listed Pres. at Start Point - 16.7 Psi (X) Wet ( ) Dry  
D MAXIMUM LISTED SPACING 20 x 20 ( ) Deluge ( ) PreAction  
E Domestic Flow Added - Gpm Sprinkler or Nozzle  
S Additional Flow Added - Gpm Make RELIABLE Model RFC49  
I Elevation at Highest Outlet - 68.167Feet Size 1/2 X 1/2 K-Factor 4.9  
G Note: Temperature Rating 165 DEG  
N DESIGN AREA #2 - 2ND FLOOR STORAGE AREA

Calculation Gpm Required 40.514 Psi Required 47.230 AT BASE OF RISER  
Summary C-Factor Used: Overhead 150 Underground 140

W Water Flow Test: Pump Data: Tank or Reservoir:  
A Date of Test - 7-28-2004 Rated Cap. Cap.  
T Time of Test - @ Psi Elev.  
E Static (Psi) - 92 Elev.  
R Residual (Psi) - 89 Other Well  
Flow (Gpm) - 1433 Proof Flow Gpm  
S Elevation - 50.0

P Location: ON OCEAN AVENUE AT READ STREET, 390-0 FROM BAY STREET

L Source of Information: PORTLAND WATER DISTRICT  
Y

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	***** Notes *****
TYP to DROP	20.02	1.101	1T 9.563	0.500	16.700		K Factor = 4.90
	20.02	150	0.0	9.562	0.0		Vel = 6.75
	0.0	0.0682	0.0	10.062	0.686		
	20.02				17.386		K Factor = 4.80
3 to 4	20.02	1.101	0.0	12.000	17.386		K Factor @ node DROP
		150	0.0	0.0	0.0		
4 to F	20.02	0.0682	0.0	12.000	0.818		Vel = 6.75
	20.49	1.101	0.0	6.000	18.204		K Factor @ node DROP
		150	0.0	0.0	0.0		
F to E	40.51	0.2512	0.0	6.000	1.507		Vel = 13.65
	0.0	1.101	4E 15.3	24.167	19.711		
		150	1T 9.563	24.863	3.754		
	40.51	0.2512	0.0	49.030	12.314		Vel = 13.65
E to RT	0.0	1.101	1E 3.825	1.417	35.779		
		150	0.0	3.825	0.0		
	40.51	0.2512	0.0	5.242	1.317		Vel = 13.65
RT to RB	0.0	1.38	1Z 3.0	8.500	37.096		
		120	0.0	3.000	8.681		* Fixed loss = 5
	40.51	0.1263	0.0	11.500	1.453		Vel = 8.69
RB to X	0.0	1.314	1E 2.247	80.000	47.230		
		150	1T 4.495	6.742	0.0		
	40.51	0.1061	0.0	86.742	9.207		Vel = 9.58
X to X1	0.0	6.16	1T 43.037	360.000	56.437		
		140	0.0	43.037	0.0		
	40.51	0.0001	0.0	403.037	0.026		Vel = 0.44
X1 to X2	0.0	12.34	1T 93.767	390.000	56.463		
		140	0.0	93.767	0.0		
	40.51	0.0	0.0	483.767	0.001		Vel = 0.11
X2 to TEST	0.0	6.16	0.0	30.000	56.464		
		140	0.0	0.0	0.433		
	40.51	0.0001	0.0	30.000	0.002		Vel = 0.44
	0.0						
	40.51				56.899		K Factor = 5.37





Date: 2010-01-08  
Static PSI: 90  
Residual PSI: 0  
Test Flow (GPM): 0  
Flow Hydrant:  
Flow at 20 PSI (GPM):

Residual PSI: 0  
Test Flow (GPM): 1162  
Flow Hydrant: POD-HYD01528  
Flow at 20 PSI (GPM): 0

POD-HYD11861 (WS003625)

Date: 2010-01-08  
Static PSI: 90  
Residual PSI: 0  
Test Flow (GPM): 0  
Flow Hydrant:  
Flow at 20 PSI (GPM):

D-HYD11881 (WS003838)

Date: 2010-09-07  
Static PSI: 84  
Residual PSI: 0  
Test Flow (GPM): 0  
Flow Hydrant:  
Flow at 20 PSI (GPM):

POD-HYD01449 (WS002094)

Date: 1993-08-12  
Static PSI: 77  
Residual PSI: 0  
Test Flow (GPM): 1075  
Flow Hydrant: POD-HYD01449  
Flow at 20 PSI (GPM): 0

Date: 1988-07-11  
Static PSI: 80  
Residual PSI: 0  
Test Flow (GPM): 1277  
Flow Hydrant: POD-HYD01449  
Flow at 20 PSI (GPM): 0

POD-HYD11879 (WS002812)

Date: 2010-08-23  
Static PSI: 85  
Residual PSI: 0  
Test Flow (GPM): 0  
Flow Hydrant:  
Flow at 20 PSI (GPM):

POD-HYD01447 (WS003158)

Date: 1993-08-12  
Static PSI: 74  
Residual PSI: 0  
Test Flow (GPM): 1000  
Flow Hydrant: POD-HYD01447  
Flow at 20 PSI (GPM): 0

Date: 1988-07-11  
Static PSI: 80  
Residual PSI: 0  
Test Flow (GPM): 1233  
Flow Hydrant: POD-HYD01447  
Flow at 20 PSI (GPM): 0

POD-HYD11862 (WS001115)

Date: 2010-01-08  
Static PSI: 90  
Residual PSI: 0  
Test Flow (GPM): 0  
Flow Hydrant:  
Flow at 20 PSI (GPM):

POD-HYD01220 (WS003536)

Date: 2004-07-28  
Static PSI: 93  
Residual PSI: 0  
Test Flow (GPM): 1433  
Flow Hydrant: POD-HYD01220  
Flow at 20 PSI (GPM): 0

Date: 1993-08-12  
Static PSI: 74  
Residual PSI: 0  
Test Flow (GPM): 1288  
Flow Hydrant: POD-HYD01220  
Flow at 20 PSI (GPM): 0

Date: 1988-07-07  
Static PSI: 78

POD-HYD012


Date: 2003-04  
Static PSI: 90  
Residual PSI:  
Test Flow (GPM):  
Flow Hydrant:  
Flow at 20 PSI (GPM):

Date: 1993-08  
Static PSI: 74  
Residual PSI:  
Test Flow (GPM):  
Flow Hydrant:  
Flow at 20 PSI (GPM):

Date: 1988-07  
Static PSI: 80  
Residual PSI:  
Test Flow (GPM):  
Flow Hydrant:  
Flow at 20 PSI (GPM):

POD-

Date:  
Static  
Resid  
Test






Water Supply Curve (C)

Sprinkler Systems, Inc.  
KING RESIDENCE

Page 12  
Date 12-9-2011

City Water Supply:  
 C1 - Static Pressure : 92  
 C2 - Residual Pressure: 89  
 C2 - Residual Flow : 1433

Demand:  
 D1 - Elevation : 7.868  
 D2 - System Flow : 40.5141  
 D2 - System Pressure : 56.899  
 Hose ( Adj City ) : \_\_\_\_\_  
 Hose ( Demand ) : \_\_\_\_\_  
 D3 - System Demand : 40.5141  
 Safety Margin : 35.097



Pressure / Flow Summary - STANDARD

Sprinkler Systems, Inc.  
KING RESIDENCE

Page 10  
Date 12-9-2011

Node No.	Elevation	K-Fact	Pt Actual	Pn	Flow Actual	Density	Area	Press Req.
TYP	0.0	4.9	16.7	na	20.02	0.05	400	16.7
3	68.167	K = K @ DROP	17.39	na	20.02			
4	68.167	K = K @ DROP	18.2	na	20.49			
F	68.167		19.71	na				
E	59.5		35.78	na				
RT	59.5		37.1	na				
RB	51.0		47.23	na				
X	51.0		56.44	na				
X1	51.0		56.46	na				
X2	51.0		56.46	na				
TEST	50.0		56.9	na				

The maximum velocity is 13.65 and it occurs in the pipe between nodes 4 and F



... Fire Protection by Computer Design

Sprinkler Systems, Inc.  
2-4 Avon Street  
P.O. Box 1285  
Lewiston, Maine 04240  
207-782-0104

Job Name : KING RESIDENCE  
Building :  
Location : 23 BAY STREET, PORTLAND, MAINE 04103  
System : 1 OF 1  
Contract : 11083  
Data File : KINGRES211083.wxf

Hyd. Ref. Point	Qa  Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
-----------------------	--------------	----------------------	---------------------------	-------------------------	----------------	----------------	-------	-------	-------

26.13

40.064

K Factor = 4.13

Pressure / Flow Summary - STANDARD

Sprinkler Systems, Inc.  
KING RESIDENCE

Page 4  
Date 12-9-2011

Node No.	Elevation	K-Fact	Pt Actual	Pn	Flow Actual	Density	Area	Press Req.
TYP	0.0	4.9	7.04	na	13.0	0.05	260	7.0
1	70.167	K = K @ DROP	7.35	na	13.0			
2	70.167	K = K @ DROP	7.5	na	13.13			
A	70.167		9.01	na				
B	59.5		16.72	na				
C	59.5		18.69	na				
D	59.5		22.89	na				
E	59.5		25.61	na				
RT	59.5		26.2	na				
RB	51.0		35.53	na				
X	51.0		39.62	na				
X1	51.0		39.63	na				
X2	51.0		39.63	na				
TEST	50.0		40.06	na				

The maximum velocity is 8.81 and it occurs in the pipe between nodes 2 and A

HYDRAULIC DESIGN INFORMATION SHEET

Name - KING RESIDENCE Date - 12-9-2011  
Location - 23 BAY STREET, PORTLAND, MAINE 04103  
Building - System No. - 1 OF 1  
Contractor - REDFERN PROPERTIES Contract No. - 11083  
Calculated By - SCOTT E. GARLAND Drawing No. - 1 OF 1  
Construction: (X) Combustible ( ) Non-Combustible Ceiling Height 9-8  
OCCUPANCY - RESIDENTIAL - SINGLE FAMILY DWELLING

S Type of Calculation: ( )NFPA 13 Residential ( )NFPA 13R (X)NFPA 13D  
Y Number of Sprinklers Flowing: ( )1 (X)2 ( )4 ( )  
S ( )Other  
T ( )Specific Ruling Made by Date  
E  
M Listed Flow at Start Point - 13.0 Gpm System Type  
Listed Pres. at Start Point - 7.0 Psi (X) Wet ( ) Dry  
D MAXIMUM LISTED SPACING 16 x 16 ( ) Deluge ( ) PreAction  
E Domestic Flow Added - Gpm Sprinkler or Nozzle  
S Additional Flow Added - Gpm Make RELIABLE Model RFC49  
I Elevation at Highest Outlet - 70.167Feet Size 1/2 X 1/2 K-Factor 4.9  
G Note: Temperature Rating 165 DEG  
N DESIGN AREA #1 - 2ND FLOOR BATHROOM & STAIRS

Calculation Gpm Required 26.135 Psi Required 35.526 AT BASE OF RISER  
Summary C-Factor Used: Overhead 150 Underground 140

W Water Flow Test: Pump Data: Tank or Reservoir:  
A Date of Test - 7-28-2004 Rated Cap. Cap.  
T Time of Test - @ Psi Elev.  
E Static (Psi) - 92 Elev.  
R Residual (Psi) - 89 Other Well  
Flow (Gpm) - 1433 Proof Flow Gpm  
S Elevation - 50.0

P Location: ON OCEAN AVENUE AT READ STREET, 390-0 FROM BAY STREET

L Source of Information: PORTLAND WATER DISTRICT  
Y