



- NOTES**
1. TOPOGRAPHIC AND BOUNDARY SURVEY INFORMATION FOR THIS PROJECT WAS PROVIDED BY LEMUS & WATSON, INC., WESTBROOK, ME. ON 04/09/04. HARRIMAN ASSOCIATES HAS REVIEWED THIS INFORMATION.
  2. SEE DRAWING C50.1, SITE DETAILS, FOR STANDARD SITE LEGEND.
  3. CONTRACTOR SHALL VERIFY SITE CONDITIONS, INCLUDING THE PRESENCE OF ASBESTOS AND OTHER HAZARDOUS MATERIALS, PRIOR TO COMMENCING THE WORK.
  4. PRIOR TO REMOVAL OF UTILITIES, VERIFY UTILITY REPORT DISCREPANCIES TO THE ARCHITECT FOR UTILITY LOCATIONS.
  5. SOME EXISTING PILES COULD BE ASBESTOS CEILING PIPE. HANDLE AND REMOVE ASBESTOS MATERIALS WITH CARE AND IN ACCORDANCE WITH APPLICABLE OSHA AND SAFETY STANDARDS.

- UTILITY LOCATION REQUIREMENTS**
- PRIOR TO EXCAVATION, VERIFY THE UNDERGROUND UTILITIES, PIPES, STRUCTURES, AND FACILITIES. PROVIDE THE FOLLOWING MINIMUM MEASURES:
- A. PRE-MARK THE BOUNDARIES OF YOUR PLANNED EXCAVATION WITH WHITE PAINT, FLAGS OR STAKES, SO UTILITY CREWS KNOW WHERE TO MARK THEIR LINES.
  - B. CALL DIG SAFE, AT 1-888-DIGSAFE, AT LEAST THREE BUSINESS DAYS - BUT NO MORE THAN 30 CALENDAR DAYS - BEFORE STARTING WORK. DON'T ASSUME SOMEONE ELSE WILL MAKE THE CALL.
  - C. IF BLASTING, NOTIFY DIG SAFE AT LEAST ONE BUSINESS DAY IN ADVANCE.
  - D. WAIT THREE BUSINESS DAYS FOR LINES TO BE LOCATED AND MARKED WITH COLOR-CODED CORNER FLAGS OR STAKES. NOTE THE COLOR OF THE MARKS AND THE TYPE OF UTILITIES THEY INDICATE. TRANSFER THESE MARKS TO THE AS-BUILT DRAWINGS.
  - E. CONTACT THE LANDOWNER AND OTHER "NON-MEMBER" UTILITIES (WATER, SEWER, GAS, ETC.), FOR THEM TO MARK THE LOCATIONS OF THEIR UNDERGROUND FACILITIES. TRANSFER THESE MARKS TO THE AS-BUILT DRAWINGS.
  - F. RE-NOTIFY DIG SAFE AND THE NON-MEMBER UTILITIES IF THE DIGGING, DRILLING OR BLASTING DOES NOT OCCUR WITHIN 30 CALENDAR DAYS, OR IF THE MARKS ARE LOST DUE TO WEATHER CONDITIONS, SITE WORK ACTIVITY OR ANY OTHER REASON.
  - G. HAND DIG WITHIN 18 INCHES IN ANY DIRECTION OF ANY UNDERGROUND LINE UNTIL THE LINE IS EXPOSED. MECHANICAL METHODS MAY BE USED FOR INITIAL SITE PENETRATION, SUCH AS REMOVAL OF PAVEMENT OR ROCK.
  - H. DIG SAFE REQUIREMENTS ARE IN ADDITION TO TOWN, CITY AND/OR STATE DOT STREET OPENING PERMIT REQUIREMENTS.
  - I. FOR COMPLETE DIG SAFE REQUIREMENTS, CALL THE PUC OR VISIT THEIR WEBSITE.
  - J. IF YOU DAMAGE, DISLOCATE OR DISTURB ANY UNDERGROUND UTILITY LINE, IMMEDIATELY NOTIFY THE AFFECTED UTILITY. IF DAMAGE CREATES SAFETY CONCERNS, CALL THE FIRE DEPARTMENT AND TAKE IMMEDIATE STEPS TO SAFEGUARD HEALTH AND PROPERTY.
  - K. ANY TIME AN UNDERGROUND LINE IS DAMAGED OR DISTURBED, OR IF LINES ARE IMPROPERLY MARKED, YOU MUST FILE AN INCIDENT REPORT WITH THE PUC. FOR AN INCIDENT REPORT FORM VISIT WWW.STATE.ME.US/MPUC OR CALL THE PUC AT 1-800-482-4689.

**BORINGS TO BEDROCK BY MARI DRILLING AND BLASTING**  
 APRIL 9, 2004

BORING NO.	GROUND ELEV.	DEPTH OF BORING (FT)	APPROX. BEDROCK ELEV.
NR-1	48.21	8	41
NR-2	48.24	9	37.5
NR-3	48.74	11	40.5
NR-4	48.53	7	42.5
NR-5	48.62	7	41.5
NR-6	48.39	8	43.5
NR-7	48.17	6	42.5
NR-8	48.20	6	42
NR-9	47.81	6	42
NR-10	47.97	5	42.5
NR-11	47.68	5.5	42
NR-12	47.40	7	40.5
NR-13	48.66	6	40
NR-14	45.93	6	41
NR-15	45.93	6	38.5
NR-16	48.72	6	40
NR-17	48.30	8	38.5
NR-18	48.30	8	38.5
NR-19	48.69	9	38.5
NR-20	46.12	12	34
NR-21	46.54	10	35.5
NR-22	48.47	12	36
NR-23	48.47	10	36
NR-24	44.08	7	35
NR-25	44.79	12	33
NR-26	44.22	12	33

FOUNDATION WAS LOCATED WHERE PRACTICAL. LINES ARE SUBJECT TO VARIATIONS BETWEEN POINTS LOCATED. STONE FOUNDATION LOCATION.

