

Mark	Date	Description
-	05-28-04	ISSUED FOR BID
-	05-17-04	OWNER REVIEW

Issue Dates

Drawing Status

- MECHANICAL DEMOLITION NOTES**
- GENERAL HVAC EQUIPMENT AND PIPING IS TO REMAIN UNLESS NOTED OTHERWISE.
- MECHANICAL DEMOLITION KEYED NOTES**
- STEAM BOILER AND BRECHING TO BE REMOVED.
 - CONDENSATE RECEIVER TO BE REPLACED.
 - TEMPORARY A/C AIR COMPRESSOR TO BE REPLACED AND RELOCATED TO NEW BOILER ROOM. EXTEND PNEUMATIC LINES TO NEW LOCATION.
 - CONDENSING FUEL OIL TANK AND PIPING TO BE REMOVED BY GENERAL CONTRACTOR.
 - STEAM AIR COMPRESSOR PIPING TO BE REMOVED AS INDICATED.
 - STEAM OR CONDENSATE PIPING TO BE REMOVED AS INDICATED.
 - FUEL OIL PUMP SET TO BE REMOVED.
 - FUEL OIL PIPING MOUNTED ALONG WALL TO BE REMOVED AS INDICATED.
 - FUEL OIL PIPING IN TROCH TO BE REMOVED AS INDICATED.
 - FUEL OIL PIPING AT FLOOR TO BE REMOVED AS INDICATED.
 - MANGONED CONDENSATE TANK TO BE REMOVED.
 - GAS OIL HEATER AND BRECHING TO BE REMOVED.
 - OW STORAGE TANK TO BE REMOVED.
 - PNEUMATIC CONTROL PANEL TO BE RELOCATED TO THE NEW BOILER ROOM EXTEND LINES AS NECESSARY.
 - 3/4" X 6" COMBUSTION AIR LAUNTERS TO BE REMOVED.
 - MANGONED A/C AIR COMPRESSOR TO BE REMOVED.
 - AIR DRYER TO BE RELOCATED TO NEW BOILER ROOM.
 - FUEL OIL FILL AND VENT TO BE REMOVED AS INDICATED.
 - STEAM FTR OR CONNECTOR AND CONTROLS TO BE REMOVED. CAP LINES BELOW FLOOR AND PROVIDE END OF MAIN DRAIN TO NEW BOILER ROOM.
 - STEAM FTR OR CONNECTOR TO REMAIN.
 - EXHAUST FAN AND ASSOCIATED GRILLER, CONTROLS AND DUCTWORK TO BE REMOVED.
 - UNIT VENTILATOR AND CONTROLS TO BE REMOVED. CAP LINES BELOW FLOOR AND PROVIDE END OF MAIN DRAIN.
 - UNIT VENTILATOR AND CONTROLS TO BE REMOVED. THE NEW UNIT INTO EXISTING S AND OR LINES.
 - REPLACE EXISTING 1"-1/2" FAN TRAP IN THIS AREA WITH NEW UNIT.
 - EXHAUST FAN TO BE RELOCATED. RECONNECT ALL CONTROLS AT NEW LOCATION.
 - UNIT VENTILATOR TO BE RELOCATED. RECONNECT CONTROLS AT NEW LOCATION.
 - UPPER AND LOWER LEVELS TO BE REMOVED.
 - REEL FOOD AND DUCTWORK TO BE REMOVED.

