



NOTES:

- THIS IS NOT A SURVEY.
- PLAN REFERENCES: A) BACK COVE ESTATES SLOPE RE-CONSTRUCTION GRADING & EROSION CONTROL PLAN, PREPARED FOR FORESIDE REAL ESTATE MANAGEMENT, INC. BY TERRADYN CONSULTANTS, LLC DATED 11/18/12 LAST REVISED 10/1/2013. (SHEET 1 OF 2).

PLANTING METHODOLOGY
All species of woody plants to be used have been chosen for their attractiveness to native wildlife, and their abilities to stabilize disturbed areas. The species listed below all occur naturally within the region, and no exotic or potentially nuisance species will be used. Plantings will be done by hand to help assure their successful establishment. Plantings may need to be postponed until spring. Ideal planting times are early spring.

SPECIES TO BE PLANTED AS LIVE STAKES
(A combination of the following species to be planted)

Common Name	Scientific Name
Black Willow	<i>Salix nigra</i>
Silky Willow	<i>Salix sericea</i>
Red Osier dogwood	<i>Cornus stolonifera</i>
Silky Dogwood	<i>Cornus amomum</i>
Speckled Alder	<i>Alnus incana</i>

LEGEND

- EXISTING CONTOUR
- PROPOSED CONTOUR
- EXISTING EDGE OF PAVEMENT
- STREAM
- BORING
- EXISTING TREE
- EXISTING WETLAND

NO.	DATE	DESCRIPTION	BY
01	5/24/2016	ADDED PLANTING METHODOLOGY	DH

**BACK COVE ESTATES
CONDOMINIUM ASSOCIATION
BANK STABILIZATION**

EAST ROADWAY
PORTLAND, MAINE

PREPARED BY:
JONES ASSOCIATES INC.
Foresters, Surveyors and Environmental Consultants

PLAN DATE:
NOVEMBER 25, 2015
SCALE: AS NOTED
PROJ. #: 15-049PD

280 POLAND SPRING ROAD, AUBURN, MAINE 04210
(207) 241-0235

S-1