

- D25 ENLARGE EXISTING DOOR OPENING. PARTITION IS BELIEVED TO BE PLASTER ON GYPSUM LATH OVER METAL TRUSS STUD.
- D26 REMOVE EXISTING DRYWALL AND STEEL STUD PARTITION.
- D27 REMOVE DOOR, FRAME, AND HARDWARE. SALVAGE DOOR, FRAME, AND HARDWARE FOR REUSE.
- D28 REMOVE ACCORDIAN DOOR.
- D29 REMOVE EXISTING SHELVING.
- D30 REMOVE ALL TOILET PARTITIONS IN THIS ROOM.
- D31 REMOVE ALL PLUMBING FIXTURES IN THIS ROOM.
- D32 REMOVE ALL PARTITIONS IN THIS ROOM. PARTITIONS ARE BELIEVED TO BE MUDSET CERAMIC TILE OVER PLASTER ON GYPSUM LATH OVER METAL TRUSS STUD.
- D33 REMOVE ALL CERMIC TILE FROM PARTITIONS TO REMAIN IN THIS ROOM. TILE IS BELIEVED TO BE MUDSET CERAMIC TILE OVER PLASTER ON GYPSUM LATH OVER METAL TRUSS STUD.
- D34 REMOVE ALL CERAMIC TILE FLOORING IN THIS ROOM. FLOORING IS BELIEVED TO BE MUDSET CERAMIC TILE OVER CONCRETE SLAB.
- D35 REMOVE ELEVATED PORTION OF CONCRETE FLOOR SLAB IN THIS ROOM. SECTION IS APPROXIMATELY 6 INCHES HIGH. REMOVE DOWN TO EXISTING FLOOR SLAB LEVEL.
- D36 REMOVE EXISTING DRAWER CABINETS FOR RELOCATION TO ART STORAGE ROOM 103.
- D37 REMOVE GENERATOR AND TRANSFER SWITCH PANEL FOR RELOCATION TO ART STORAGE ROOM 103.