

PIPING ABOVE.

- D11
- REMOVE ALL SUSPENDED TILE CEILING IN THIS ROOM TO PROVIDE ACCESS TO PIPING ABOVE.
- D12
- REMOVE SECTION OF SUSPENDED PLASTER CEILING TO THE EXTENT INDICATED TO PROVIDE ACCESS TO PIPING ABOVE.
- D13
- REMOVE EXISTING CARPET AND PAD.
- D14
- REMOVE EXISTING VINYL WALLCOVERING AND ADHESIVE.
- D15
- REMOVE EXISTING RUBBER BASE.
- D16
- REMOVE CEILING AND SUSPENSION SYSTEM IN THIS ROOM. CEILING IS BELIEVED TO BE PLASTER AND METAL LATH ON METAL TRUSS SUSPENSION SYSTEM.
- D17
- REMOVE EXISTING WINDOW COVERINGS.
- D18
- REMOVE LAVATORY AND VANITY CABINET.
- D19
- REMOVE EXISTING WATER CLOSET
- D20
- REMOVE EXISTING PARTITIONS THIS ROOM. PARTITIONS ARE BELIEVED TO BE PLASTER ON GYPSUM LATH OVER METAL TRUSS STUD.
- D21
- REMOVE PIPING AND CAP OFF BELOW FLOOR, BEHIND WALL, OR ABOVE CEILING.
- D22
- REMOVE BASEBOARD AND CABINET HEATING ELEMENTS.
- D23
- CUT OPENING IN MASONRY WALL FOR UNIT VENTILATOR INTAKE.
- D24
- REMOVE SUSPENDED TILE CEILING IN CORRIDOR. SALVAGE ACRYLIC PANELS AND FRAMES FOR REINSTALLATION IN NEW SUSPENDED CEILING.
- D25
- ENLARGE EXISTING DOOR OPENING. PARTITION IS BELIEVED TO BE PLASTER ON GYPSUM LATH OVER

MAR

Rev

No.