



Estimate

6.21.16

Frost02

Brian Frost
Portland, ME

Estimate Total: \$8,500

10' x 14' Shed Estimate

Specs:

- 4" concrete slab
- 2x4x8 walls 16" on center
- 7/16 OSB plywood wrapped in Typar
- 2x8 rafters 16" on center, 12 pitch
- 8" overhang on all 4 sides of roof
- 5/8 OSB plywood sheathing
- Grace Ice & Water on entire roof
- 30-yr architectural shingles (will match house shingles)
- Ivy green siding to match house

Notes:

- Entry door still be discussed and decided upon (\$500 has been budged in estimate for door)

ESTIMATE TOTAL:

\$8,500