

WINDOW SCHEDULE

	TYPE	MAKE	MODEL	TYPE	R.O. WIDTH	R.O. HEIGHT	HEAD HEIGHT	REMARKS
	A	WOOD-ULTREX INTEGRITY	IAWN 2931	AWNING	2'-5"	2'-7 5/8"	6'-8"	SDL PATTERN PER EXT. ELEVATIONS.
	B	WOOD-ULTREX INTEGRITY	IAWN 3735	AWNING	3'-1"	2'-11 5/8"	7'-6"	SDL PATTERN PER EXT. ELEVATIONS.
	C	WOOD-ULTREX INTEGRITY	POLYGON	FIXED	SEE BELOW	SEE BELOW	10'-7"	
	D	WOOD-ULTREX INTEGRITY	POLYGON	FIXED	SEE BELOW	SEE BELOW	12'-2"	
	E	WOOD-ULTREX INTEGRITY	POLYGON	FIXED	SEE BELOW	SEE BELOW	10'-7"	

WINDOW NOTES:

1. THE BUILDER SHALL PROVIDE PULTRUDED FIBERGLASS WINDOWS OF TYPES AND SIZES AS NOTED BY THE DRAWINGS AND WINDOW SCHEDULE.
2. ALL AWNING AND CASEMENT WINDOWS SHALL MEET OR EXCEED NDMA DESIGN PRESSURE RATING DP50.
3. ALL WINDOWS SHALL BE PROVIDED WITH DOUBLE-PANE, LOW-E GLASS WITH A CENTER OF GLASS "U" VALUE OF 0.30 (MINIMUM).
4. ALL WINDOWS SHALL BE WOOD-ULTREX SERIES INTEGRITY BY MARVIN WHITE EXTERIOR WITH PRE-FINISH WHITE INTERIOR. INTERIOR WINDOW HARDWARE FINISH SHALL BE STANDARD WHITE.
CONFIRM ALL COLORS/FINISHES WITH OWNER PRIOR TO ORDERING WINDOWS.
5. ALL OPERABLE WINDOWS SHALL BE PROVIDED WITH INSECT SCREENS. SCREEN MATERIAL TO BE FIBERGLASS SCREEN CLOTH. SCREEN FRAMES TO BE STANDARD WHITE FINISH.
6. BUILDER MUST CONFIRM ALL SIZES, ROUGH OPENING DIMENSIONS, AND INSTALLATION DETAILS BEFORE COMMENCING CONSTRUCTION. NOTIFY ARCHITECT OF ANY DISCREPANCIES BEFORE PROCEEDING AND/OR ORDERING WINDOWS. SUBMIT SHOP DRAWINGS TO ARCHITECT.
7. ALL WINDOWS MUST BE SHIMMED, FLASHED, INSULATED, CAULKED WITH POLYURETHANE ADHESIVE CAULK, AND SEALED AGAINST AIR INFILTRATION TO THE HIGHEST QUALITY OF WORKMANSHIP AND MATERIALS. INSTALL 6" OR 8" WIDE 3M BRAND FLASHING TAPE AT ALL WINDOW OPENINGS - FOLLOW ALL MANUF. RECOMMENDATIONS.
8. PRIOR TO COMMENCING WINDOW INSTALLATION, A WINDOW PRE-INSTALLATION MEETING SHALL BE HELD ON-SITE WITH THE BUILDER, SUPERINTENDENT/FOREMAN, MARVIN REP. AND ARCHITECT.
10. PROVIDE TEMPERED GLASS WHERE REQUIRED BY CODE. ALL REQUIRED LOCATIONS MAY NOT BE LISTED ON WINDOW SCHEDULE ABOVE.

