

INTRODUCTION

SICO Universal Steps are designed to work with all SICO stage products.

Dual Height, Articulating and Venue Steps are available in a variety of sizes to match your stage height.

Dual Height Steps:

- Dual Height Steps are available to accommodate various stage heights. Steps range from 12" (305 mm) to 32" (610 mm) in fixed heights.

STEP MODEL	STEP RISER HEIGHT	ATTACHES TO STAGE HEIGHT:
2 step model	6" (152 mm)	12" or 18" (305 mm-457 mm)
2 step model	8" (203 mm)	16" or 24" (406 mm-610 mm)
3 step model	6" (152 mm)	18" or 24" (457 mm-610 mm)
3 step model	8" (203 mm)	24" or 32" (610 mm-813 mm)

- Parts of the step include, guardrails, clamp and casters.

See page 4 for detailed installation instructions.

Articulating Steps:

- Articulating Steps are available to accommodate various stage heights from 12" (305 mm) to 56" (1,422 mm).

STEP MODEL	STEP RISER HEIGHT:	ATTACHES TO STAGE HEIGHT:
3 step model	4" to 8" (102 mm-203 mm)	12" to 24" (305 mm-610 mm)
4 step model	4" to 8" (102 mm-203 mm)	16" to 32" (406 mm-813 mm)
5 step model	4" to 8"	20" to 40"

