

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that
CITY OF PORTLAND

Located at
427 OCEAN AVE

PERMIT ID: 2014-01877 ISSUE DATE: 09/03/2014 CBL: 159 G001001

has permission to **Tent permit application, Race for the Cure set upon Sept 12, 2014 and break down on Sept 14, 2014 - 1 stage: 10- 10'x10' tents; 1- 10'x20' tent; 1-20'x20' tent; 1- 30'x30' tent; 1- 40'x40' tent - see plan**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ David Petruccelli

/s/ Tammy Munson

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning
Public City Park

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2014-01877	Date Applied For: 08/21/2014	CBL: 159 G001001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: Public Ciy Park - Payson Park		Proposed Project Description: Tent permit application, Race for the Cure setupon Sept 12, 2014 and break down on Sept 14, 2014 - 1 stage: 10- 10'x10' tents; 1- 10'x20' tent; 1-20'x20' tent; 1- 30'x30' tent; 1- 40'x40' tent - see plan		
Dept: Zoning	Status: Approved	Reviewer: Marge Schmuckal	Approval Date: 08/21/2014	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
Dept: Building	Status: Approved	Reviewer: Tammy Munson	Approval Date: 08/22/2014	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
Dept: Fire	Status: Approved w/Conditions	Reviewer: David Petrucci	Approval Date: 09/02/2014	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) Installation shall comply with City Code Chapter 10. All construction shall comply with City Code Chapter 10.				
2) 11.11.3 Location and Spacing.				
11.11.3.1 There shall be a minimum of 10 ft (3050 mm) between stake lines.				
11.11.3.2 Adjacent tents shall be spaced to provide an area to be used as a means of emergency egress. Where 10 ft (3050 mm) between stake lines does not meet the requirements for means of egress, the distance necessary for means of egress shall govern.				
11.11.3.3 Tents not occupied by the public and not used for the storage of combustible material shall be permitted to be erected less than 10 ft (3050 mm) from other structures where the authority having jurisdiction deems such close spacing to be safe from hazard to the public.				

- 3) 12.4.5 Stages and Platforms. See 3.3.262 and 3.3.209.
- 12.4.5.1 Materials and Design.
- 12.4.5.1.1 Materials used in the construction of platforms and stages shall conform to the applicable requirements of the local building code.
- 12.4.5.1.2 Stage stairs shall be permitted to be of combustible materials, regardless of building construction type.
- 12.4.5.2 Platform Construction.
- 12.4.5.2.1 Temporary platforms shall be permitted to be constructed of any materials.
- 12.4.5.2.2 The space between the floor and the temporary platform above shall not be used for any purpose other than the electrical wiring to platform equipment.
- 12.4.5.2.3 Permanent platforms shall be of the materials required for the building construction type in which the permanent platform is located, except that the finish floor shall be permitted to be of wood in all types of construction.
- 12.4.5.2.4 Where the space beneath the permanent platform is used for storage or any purpose other than equipment wiring or plumbing, the floor construction shall not be less than 1-hour fire resistive.
- 12.4.5.3 Stage Construction.
- 12.4.5.3.1 Regular stages shall be of the materials required for the building construction type in which they are located. In all cases, the finish floor shall be permitted to be of wood.
- 12.4.5.3.2 Legitimate stages shall be constructed of materials required for Type I buildings, except that the area extending from the proscenium opening to the back wall of the stage, and for a distance of 6 ft (1830 mm) beyond the proscenium opening on each side, shall be permitted to be constructed of steel or heavy timber covered with a wood floor not less than 1 1/2 in. (38 mm) in actual thickness.
- 12.4.5.3.3 Openings through stage floors shall be equipped with tight-fitting traps with approved safety locks, and such traps shall comply with one of the following:
- The traps shall be of wood having an actual thickness of not less than 1 1/2 in. (38 mm).
 - The traps shall be of a material that provides fire and heat resistance at least equivalent to that provided by wood traps having an actual thickness of not less than 1 1/2 in. (38 mm).