

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that
CITY OF PORTLAND

Located at
427 OCEAN AVE

PERMIT ID: 2014-02082 **ISSUE DATE:** 09/25/2014 **CBL:** 159 G001001

has permission to **2014 Alzheimers Walk; set up 09/26/2014 take down 09/27/2014. 2 20x40 tents, 1 20x50 and 1 stage.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ David Petrucci

Fire Official

/s/ Laurie Leader

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning
Public City Park

Building Inspections

Fire Department

PERMIT ID: 2014-02082

Located at: 427 OCEAN AVE

CBL: 159 G001001

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2014-02082	Date Applied For: 09/10/2014	CBL: 159 G001001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: Public City Park -Payson Park		Proposed Project Description: 2014 Alzheimers Walk; set up 09/26/2014 take down 09/27/2014. 1 20x40 tents, 1 20x50 and 1 stage.		
Dept: Zoning Status: Approved Reviewer: Marge Schmuckal Approval Date: 09/16/2014 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions:				
Dept: Building Status: Approved w/Conditions Reviewer: Laurie Leader Approval Date: 09/24/2014 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: <ol style="list-style-type: none"> 1) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work. 2) A separate permit is required for any temporary electrical work. 3) Temporary structures and uses shall conform to the structural strength, fire safety, means of egress, accessibility, light, ventilation and sanitary requirements of this code as necessary to ensure public health, safety and general welfare. 4) This permit DOES NOT authorize any construction activities. The tent/stage must be removed at the end of the event. 				
Dept: Fire Status: Approved w/Conditions Reviewer: David Petrucci Approval Date: 09/16/2014 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: <ol style="list-style-type: none"> 1) Fire extinguishers will be required per NFPA 10. 2) Tents shall have an approved fire resistant rating and maintain 10' between stake lines. No smoking or open flame allowed within 10'. Provide at least one 2A:10 BC fire extinguisher. 3) If the sides of the tents are to be enclosed at least two remotely located and marked exits shall be provided. 4) Fuel-fired heating equipment and propane tanks shall be installed outside of the tents and not within 5 feet of the tents or an exit discharge. 5) Cooking within the tents has not been reviewed or approved. 6) All tents shall meet the flame propagation performance criteria contained in NFPA 701. A certificate or other evidence of acceptance by an organization acceptable to the AHJ shall serve as evidence that the tent fabric materials have the required flame propagation performance. 7) EXITS <ol style="list-style-type: none"> a.The main entrance shall have minimum clear width of 10 feet. B.The divider in the main tent shall maintain an exit opening of 6 feet. C.A main corridor for the main tent shall be maintained a minimum of 50 inches. Where a chair is placed between a table and the corridor the measurement shall be made from the table and add 19 inches for each chair (ie. Chair at both sides 38" + 50"= 88"). 8) Tents shall have an approved fire resistant rating and maintain 10' between stake lines. No smoking or open flame allowed within 10'. Provide at least one 2A:10 BC fire extinguisher. 9) If the sides of the tents are to be enclosed at least two remotely located and marked exits shall be provided. 10 Fuel-fired heating equipment and propane tanks shall be installed outside of the tents and not within 5 feet of the tents or an exit discharge. 11 Cooking within the tents has not been reviewed and approved. 				

PERMIT ID: 2014-02082

Located at: 427 OCEAN AVE

CBL: 159 G001001

- 12 All tents shall meet the flame propagation performance criteria contained in NFPA 701. A certificate or other evidence of acceptance by an organization acceptable to the AHJ shall serve as evidence that the tent fabric materials have the required flame propagation performance.
- 13 EXITS
- a. The main entrance shall have minimum clear width of 10 feet.
 - B. The divider in the main tent shall maintain an exit opening of 6 feet.
 - C. A main corridor for the main tent shall be maintained a minimum of 50 inches. Where a chair is placed between a table and the corridor the measurement shall be made from the table and add 19 inches for each chair (ie. Chair at both sides 38" + 50" = 88").
 - D. An exit from the main tent to the outside directly across from the main entrance shall be provided. Minimum clear width shall be 6 feet.
 - E. The auction tent shall have 2 exits perpendicular from the main tent. Minimum clear width shall be 36".
 - F. The catering tent shall have one additional exit across from the main tent. Minimum clear width shall be 36".
- 14 Fire extinguishers will be required per NFPA 10.
- 15 The cooking equipment shall not be underneath the tent
- 16 12.4.5 Stages and Platforms. See 3.3.262 and 3.3.209.
- 12.4.5.1 Materials and Design.
 - 12.4.5.1.1 Materials used in the construction of platforms and stages shall conform to the applicable requirements of the local building code.
 - 12.4.5.1.2 Stage stairs shall be permitted to be of combustible materials, regardless of building construction type.
 - 12.4.5.2 Platform Construction.
 - 12.4.5.2.1 Temporary platforms shall be permitted to be constructed of any materials.
- 17 Emergency lighting and approved illuminated EXIT signs are required for events held outside of day light hours. A back up generator with transfer switch shall meet this requirement if the following is met:
- a. All lighting is powered from the generator circuit.
 - B. The lighting illuminates the face of the EXIT signs.
 - C. An auto transfer and start shall be provided or dedicated staff shall be provided for that purpose.