Price Structural Engineers, Inc.
75 Farms Edge Road
North Yarmouth, ME 04097
Tel: 207-846-0099
Fax: 207-846-1633

Project: Canning Residence	
Subject: Header Design	Sheet: 8
Date: Feb. 28, 2017	Job #: 108
Designed by: DAP	Checked by:

CITY OF PORTLAND, MAINE
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 04/21/17

1. Verify-in-Field (VIF) existing Anchor Bolts (AB). Add additional expansion bolts (½"ø typ.) such that there are a minimum of:
   a) Two A.B. between window openings
   b) One A.B. @ 4' o.c. at west foundation wall.

SK-3 WEST FOUNDATION WALL - ELEVATION