



Customer Name:
Address:

Project Name: LOTFEY
Quote Name: LOTFEY
Quote Number: 1722133
Order Date: Quote Not Ordered
PO Number:


Phone:
Fax:
Customer Information:

Comments:

RO size for Flange is for standard 1x buck with precast sill. Please contact your supplier for other Flange opening RO's.

ITEM & SIZES	LOCATION / TAG	PRODUCT DESCRIPTION	UNIT PRICE / EXTENDED PRICE
--------------	----------------	---------------------	-----------------------------

Line Item: 100-1	None Assigned	*** PRODUCT *** Row 1 1556 Double Hung - Vent - 1 Units - 35.75W x 53.5H	
Quantity: 1		*** DIMENSIONS *** 35.75W x 53.5H	
RO Size: 36.25" X 54"		*** FRAME *** East, Vinyl, Frame Type - Fin, Exterior Color - White	
Unit Size: 35.75" X 53.5"		*** GLASS *** Glazing Type - Insulated, Glass Tint - Clear, Low-E, Glass Strength - DSB	
		*** SCREEN *** Screen - Full Flexscreen, Screen Mesh Type - Clarity, Screens Packed Separately - Yes	
		*** WRAPPING *** Extension Jamb - 4 9/16 Wood, Extension Jamb Type - Primed Finger Jointed, Number of Jamb Sides - Three Sides, J-Channel - Integral	
		*** NFRC *** Series 1556::DoubleHung, U-Factor::0.31, SHGC::0.27, VT::0.51	
		*** Performance *** Series 1556::DoubleHung, Calculated Positive DP Rating::45.11, Calculated Negative DP Rating::50.13, DP Rule ID::1556 DH, Rating Type::DesignPressure, Structural Rating::R-PG30*, Water Rating::4.59, FL ID::N/A	



Unit Price: ~~██████████~~

1556 Double Hung - Vent - 3046

Extended Price: ~~██████████~~