



Notes:

1. **PROPOSED 2x8 RAFTERS** throughout Roof & DORMERS for structural & Insulation purposes.
 72" x 48 Slider Egress window
 U value = 0.33
2. Hurricane clips or structural screws to be used at all rafter to wall connections. (each Rafter)
3. Hangers to be used at Rafter to Ridge if needed.
4. All new ceilings to be 1/2" gyp. attached to 3/4" strapping directly on new rafters. (vaulted or cathedral ceilings)