

C

# WINDOW SPECS.

Customer:

Project Name: Fortier,Liz,1921930

Order Number: 185


Quote Number: 9525744

Line #	Location:	Attributes
--------	-----------	------------

15 None Assigned

## Vinyl Windows / Doors By Pella, Casement Right, 35.5 X 41.5, White

Item Price	Qty	Ext'd Price
\$292.79	1	\$292.79



Viewed From Exterior

PK #  
1994

**1: 3642 Right Casement**  
**Frame Size:** 35 1/2 X 41 1/2  
**General Information:** Standard, Vinyl, Nail Fin, 3 3/8", 1 7/16", 1 15/16"  
**Exterior Color / Finish:** White  
**Interior Color / Finish:** White  
**Glass:** Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude  
**Hardware Options:** Standard, Wash Hinge Hardware, Fold-Away Crank, White, No Limited Opening Hardware  
**Screen:** Full Screen  
**Performance Information:** U-Factor 0.26, SHGC 0.21, VLT 0.39, CPD PEL-N-135-00033-00002, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, Year Rated 08, Egress Meets Typical 5.7 sqft (E) (United States Only)  
**Grille:** GBG, No Custom Grille, 3/4" Contour, Traditional (3W3H)  
**Wrapping Information:** No Exterior Trim, No Interior Trim, Pella Recommended Clearance, Perimeter Length = 154".


Rough Opening: 36" X 42"

Line #	Location:	Attributes
--------	-----------	------------

20 None Assigned

## Vinyl Windows / Doors By Pella, Awning Vent, 23.5 X 17.5, White

Item Price	Qty	Ext'd Price
\$253.46	1	\$253.46



Viewed From Exterior

PK #  
1994

**1: 2418 Vent Awning**  
**Frame Size:** 23 1/2 X 17 1/2  
**General Information:** Standard, Vinyl, Nail Fin, 3 3/8", 1 7/16", 1 15/16"  
**Exterior Color / Finish:** White  
**Interior Color / Finish:** White  
**Glass:** Insulated Tempered Low-E Advanced Low-E Insulating Glass Argon Non High Altitude  
**Hardware Options:** Standard, Wash Hinge Hardware, Fold-Away Crank, White, No Limited Opening Hardware  
**Screen:** Full Screen  
**Performance Information:** U-Factor 0.27, SHGC 0.21, VLT 0.39, CPD PEL-N-145-00049-00002, Performance Class CW, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, Year Rated 08, Egress Not Applicable  
**Grille:** GBG, No Custom Grille, 3/4" Contour, Traditional (2W2H)  
**Wrapping Information:** No Exterior Trim, No Interior Trim, Pella Recommended Clearance, Perimeter Length = 82".

Rough Opening: 24" X 18"

For more information regarding the finishing, maintenance, service and warranty of all Pella® products, visit the Pella® website at [www.pella.com](http://www.pella.com)