

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

April 21, 2017

Responsible Party 1: BURNHAM H PAGE PO BOX 6816 SCARBOROUGH, ME 04070		Responsible Party 2: Burnham II Harold P PO BOX 2087 SCARBOROUGH , ME 04070	
Location 609 OCEAN AVE	CBL 163A B015001	Inspection Date 4/6/2017	
Inspector Mark Stewart	Inspection Type FP Routine Inspection	Status Failed	

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 5/15/2017.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
PORTLAND FIRE DEPARTMENT CHAPTER 10 SECTION 12 KNOX BOX REQUIRED; Knox Boxes are required for all buildings with fire alarm or suppression systems. Knox Box required	___/___/___
NFPA 101- 7.2.1.8.1 FIRE DOOR(S) MUST SELF-CLOSE; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. Door closer for laundry room fire door on first floor missing	
NPFA 101- 7.2.2.1.1 STAIRS REQUIRE REPAIR; Stairs shall meet the following criteria: (1) New stairs shall be in accordance with Table 7.2.2.2.1.1(a) (2) Existing stairs shall be permitted to remain in use, provided that they meet the requirements for existing stairs shown in Table 7.2.2.2.1.1(b) (3) Approved existing stairs shall be permitted to be rebuilt in accordance with the following: (a) dimensional criteria of table 7.2.2.2.1.1(b) and other stair requirements of 7.2.2 (4) The requirements for new and existing stairs shall not apply to stairs located in industrial equipment access areas where otherwise provided in 40.2.5.2. Exterior cement stairs to access apartments 11 and 12 are damaged.	___/___/___
PORTLAND FIRE DEPARTMENT CHAPTER 10 FIRE ALARM SYSTEM REQUIRES SERVICE; Fire alarm system requires service by a licensed master fire alarm company. A list of licensed master fire alarm companies can be viewed at: www.portlandmaine.gov/fireprevention . Panel door lock removed	___/___/___

Violation	Proposed Date of Completion
<p>NFPA 720- 5.5.6.1 CO ALARMS REQUIRED; The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6.</p> <p>No CO alarms present in apartments 8, 11, 12, 28 and 34.</p>	<p>___/___/___</p>
<p>NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements.</p> <p>None of the one or two bedroom apartments have smoke detectors in the sleeping areas.</p>	<p>___/___/___</p>
<p>NFPA 101- 8.2.3 FIRE RATING NOT MAINTAINED; The fire resistance of structural elements and building assemblies shall be determined in accordance with test procedures set forth in NFPA 251, ASTM E 119, ANSI/ UL 263, or other approved test methods, or analytical methods approved by the authority having jurisdiction. Materials used to construct fire resistance-rated elements and assemblies shall be limited to those permitted in this code.</p> <p>Sheetrock around newly installed Lally Column in Boiler Room needs repair.</p>	
<p>NFPA 70 MISSING BREAKER IN PANEL; Refer to NFPA 70, National Electrical Code, for information on missing breakers in an electrical panel.</p> <p>Knockout missing in Electrical Panel.</p>	
<p>CITY OF PORTLAND CODE CHAPTER 10- 21.5 HAZARDOUS MATERIALS MANAGEMENT CABINET REQUIRED; Buildings required to comply with tier 2 shall provide a hazardous materials management cabinet on the exterior of the building. This shall also comply with Section 10-21.5 of Portland City Codes. See www.portlandmaine.gov/citycode.htm.</p> <p>Oil based finishes and solvents need to be stored in a rated cabinet.</p>	
<p>FINAL DATE OF COMPLETED VIOLATION(S)</p>	<p>___/___/___</p>
<p>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</p>	<p>___/___/___</p>

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date

Responsible Party

Date

Responsible Party

SEEN AND AGREED

Date

Fire Prevention Bureau