

GENERAL NOTES:

REVISIONS:

FORESIDE ARCHITECTS LLC
 5 Fundy Road
 Falmouth, Maine 04105
 Phone: 207-781-3344
 Fax: 207-699-5564
 Online @ foresidearchitects.com

Project Status:
 Bid Set

Project Number:
 SR0712

Project Title:
 Seaside Rehab & Healthcare Center
 850 Baxter Blvd
 Portland, ME

Drawing Name:
 VRV System Equipment Schedule #2

Scale:
 1/8"=1'-0"

Date:
 10/29/12

SHEET
 M1.6

Outdoor unit information

Sign Condition	Heating Mode			System	Required actual capacity for each system			Selected Model		Rated Capacity (By Indoor unit)			Calculated Actual Capacity		Current Input		Power Source	Design Condition				
	Dry bulb temperature	Relative Humidity	Wet bulb temperature		Cooling (Total)	Heating	Ref.	Model name	Cooling	Heating	Cooling	Heating	Cooling	Heating	Cooling	Heating		Dry bulb temperature (DB)	Water temperature (DB)	Dry bulb temperature (DB)	Wet bulb temperature (WB)	Relative Humidity (RH)
72.0	68.0			First Floor	233012	252058	PUHY-P240TSMU-A	240000	270000	233007	252057	62.8-56.8	66.1-59.7	208/230V	95.0	44.6	42.8	87				
72.0	68.0			Second Fld	233012	252058	PUHY-P240TSMU-A	240000	270000	233007	252057	62.8-56.8	66.1-59.7	208/230V	95.0	44.6	42.8	87				
72.0	68.0			First Floor	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				
72.0	68.0			Second Fld	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				
72.0	68.0			First Floor	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				
72.0	68.0			Second Fld	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				
72.0	68.0			First Floor	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				
72.0	68.0			Second Fld	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				
72.0	68.0			First Floor	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				
72.0	68.0			Second Fld	-	-	PUHY-P240TSMU-A	-	-	-	-	-	-	-	-	-	-	-				

Schedule is continued from Drawing M1.5.