



Seaside Rehabilitation and Health Care

-Sliding Door Hardware and Operation Code Review Response

FORESIDE ARCHITECTS

1/21/13

ASSA ABLOY, the global leader
in door opening solutions.

102 - Door Pull 5-1/2" CTC



Available Finishes:

- ▶ White Powder Coat/WPC
- ▶ Red Powder Coat/RPC
- ▶ Black Powder Coat/BPC
- ▶ US32DMS
- ▶ US32D/630
- ▶ US32/629
- ▶ US26D/626
- ▶ US26/625
- ▶ US10B/613
- ▶ US10/612
- ▶ US4/606
- ▶ US3/605
- ▶ 315/711
- ▶ 313/710

Specifications:

Material: Aluminum, Brass, Bronze, Stainless Steel

Fastener: 1/4 -20 x 2-1/4 Thru Bolt & Finish Washer (standard 1-3/4" door).

Options:

- Back to back mounting in pairs — use BTB suffix and mounting type number (102BTB5).
- Concealed mounting single pulls — use C suffix and mounting type number (102C6).
- Advise if door thickness is other than 1-3/4".
- Mounting selections for standard duty 1/4-20 can be viewed under Mounting Details on this site.
- 2-1/2" Barrier Free clearance — use BF prefix (BF102).

Material Size: 5/8" dia.

CTC: 5-1/2"

Overall: 6-1/8"

Base: 5/8"

Projection: 2"

Clearance: 1-3/8"

Weight: 0.6 lbs.

ANSI A156.6:

*** Operation complies with 2010 ADAAG Guidelines
for door operation 309.4, force required to activate
shall be stipulated to be less than 5lbs. of applied force.**

**Door Frame Opening = 3'-4"
Door Opening Clearance = 3'-0"**

Rockwood Manufacturing Company • 300 Main Street • Rockwood, PA 15557
P 800.458.2424 • F 800.922.9212 • info@rockwoodmfg.com • www.rockwoodmfg.com
Copyright © 2008 Rockwood Manufacturing Co. All rights reserved.