

Seaside Rehabilitation and Health Care Center
Portland, Maine

SECTION 211313 - AUTOMATIC FIRE PROTECTION

PART 1 GENERAL

1.1 DESCRIPTION OF WORK

- A. Provide a new wet / dry pipe sprinkler system for the new addition. The work covered by this Section of the specifications includes the furnishing of labor, materials, equipment, transportation, permits, inspections and incidentals and the performing of operations required to design modifications, install and test a pressurized, fully supervised, wet or dry pipe fire protection system for full building protection in accordance with NFPA, IBC, and the Owner's insurance underwriter as a modification to the existing system.
- B. The building sprinkler system design shall be based on NFPA13 requirements.

1.2 RELATED DOCUMENTS

- A. The drawings and the specifications including Section 230500 "Supplemental Mechanical General Requirements" are hereby made a part of the work of this section.
- B. Drawings and general provisions of Contract including General and Supplementary Conditions and all Division 1 specification sections.

1.3 QUALIFICATIONS

- A. The Fire Protection Work shall be performed by a qualified Contractor primarily engaged in the design and installation of Fire Protection Systems. The fire protection system design shall be performed under the direction of, and sealed by, a professional engineer registered in the State of Maine or with NICET Level III (minimum) Certification.
- B. Welding qualifications of individuals installing welded piping shall be certified by the National Certified Welding Bureau for the type(s) of weld(s) proposed for use in piping assembly.

1.4 SUBMITTALS

- A. Items for which the submittal requirements of section 230500, Supplemental Mechanical General Requirements, apply are as Follows:
 - 1. Hydrant flow test.
 - 2. System components.
 - 3. Hydraulic calculations.
 - 4. Piping layout, details and control diagram.
 - 5. Flushing and testing records.
 - 6. Certificate of installation.
 - 7. Copy of Fire Protection Contractors License.
 - 8. Welding certificates of individual welding technicians.
 - 9. Sprinkler heads.
 - 10. Firestopping materials and methods.

Seaside Rehabilitation and Health Care Center
Portland, Maine

Submit hydrant flow test, equipment descriptive data, hydraulic calculations and system layout for review by the Owner's Insurance Underwriter. Submit the system layout to the Engineer for review. The Engineer's review will be limited to checking for conformance with the design concept of the project and general compliance with the contract documents and will in no way assume liability for review for compliance with codes, standards and laws.

- B. Submittal Procedures: Submittal procedures.
- C. Product Data: Submit data on product characteristics, performance criteria and limitations.
- D. Manufacturer's Installation Instructions: Submit procedure for preparation and installation.
- E. Manufacturer's Certificate: Certify products meet or exceed specified requirements.

1.5 SPRINKLER COVERAGE

- A. Sprinkler head coverage shall conform with NFPA 13 requirements for the use of the building. Coverage shall be increased accordingly where required by the Authority having jurisdiction.
- B. If the requirements of the inspection agency or the Owner's insuring agent are more rigorous than those stated herein, then the more rigorous requirements shall govern.

PART 2 PRODUCTS

2.1 SYSTEM COMPONENTS AND HARDWARE

- A. Pipe, Fittings, Joints, Hangers, Valves, Fire Department Connections, Alarms: Conform to NFPA 13, Installation of Sprinkler Systems.
- B. Sprinkler Heads:
 - 1. Interior Heated Spaces: Conform to NFPA 13, commercial quick response type. Provide semi-recessed type with white finish for acoustical tile ceilings. Sprinkler heads in GWB ceilings and Corridors shall be "concealed" type. Dry pendent or sidewall heads, where required, may be standard response type. Heads shall be centered in the ceiling tiles.
 - 2. Provide a spare head cabinet with wrenches, the amount of spare heads for each orifice size, finish, temperature classification, pattern and length furnished in the project shall be in accordance with the following schedule:

Sprinkler Heads on Project	Number of Spare heads of each type.
Less than 300	6
300-999	12
1000 or more	24
 - 3. Provide head protection guards where required.
 - 4. Sprinkler heads in unheated areas (if any) shall be dry pendent or sidewall type, or served by a glycol and water loop or separate dry-pipe system.

Seaside Rehabilitation and Health Care Center
Portland, Maine

- C. Fire Department Connection: 4” Storz, verify type and location with the Portland Fire Department.

2.2 WATER SUPPLIES

- A. Cement-lined ductile iron per NFPA13.

2.3 DEVICES

- A. Detection devices and associated wiring both within the fire protection system and to the building Fire Alarm System shall be the responsibility of the Sprinkler Contractor.

2.4 BACKFLOW PREVENTER

- A. Ames 2000SS “Silver Bullet” series, double check valve type for fire protection service.

2.5 PIPING SYSTEM IDENTIFICATION

- A. Piping system and valve identification and color coding shall be in accordance with ANSI.

PART 3 EXECUTION

3.1 PIPING LAYOUT AND DESIGN

- A. System requirements, installation requirements, design, plans, and calculations: Conform to NFPA 13, Installation of Sprinkler Systems.
- B. Sprinkler piping shall be run concealed above ceilings / soffits in occupied areas. Piping in other areas may be run exposed. Piping shall not be exposed in occupied spaces unless indicated on the drawings.
- C. Pipe penetrations through walls and floors shall be in accordance with Section 15000 - Supplemental Mechanical General Requirements. Traverse points of piping shall be escutcheoned with split chrome floor and ceiling plates and spring anchors, where visible to occupancy. Penetrations through walls shall be sleeved in accordance with Section 15000. Sleeves shall be provided by the Fire Protection Contractor.
- D. Coordinate design and layout with building structure and building systems. The work shown in the contract documents has precedence for space requirements. Work of other trades may be modified or moved only with permission of the trade involved. Costs associated with modifications or relocations shall be the same as for "Substitutions" Section 15000.
- E. The Architect shall review the proposed system layout and reserve the right to relocate heads, substitute head system and in general review final layout for components visible in occupied spaces.

Seaside Rehabilitation and Health Care Center
Portland, Maine

3.2 SYSTEM ACCEPTANCE

- A. Approval, flushing, hydrostatic testing, instructions, and certificates of installation: Conform to NFPA 13, Installation of Sprinkler Systems.
- B. Disinfect the water piping in accordance with AWWA C601. Fill the piping systems with solution containing a minimum of 50 parts per million of available chlorine and allow solution to stand for minimum of 24 hours. Repeat disinfection if chlorine residual is less than 10 parts per million after 24 hours. Flush the solution from the systems with clean water until maximum residual chlorine contents is not greater than 0.2 parts per million.
- C. Closing in Work:
 - 1. General: Cover up or enclose work after it has been properly and completely reviewed.
 - 2. No additional cost to the Owner will be allowed for uncovering and recovering, work that is covered or enclosed prior to required review and acceptance.
- D. Cleanup and Corrosion Prevention:
 - 1. Upon completion of the work thoroughly clean and flush piping systems to the sewer with water.
 - 2. Piping and equipment shall be thoroughly cleaned. Dirt, dust, and debris shall be removed and the premises left in a clean and neat condition.
 - 3. Before uncovered piping is permitted to be concealed, corrosion and rust shall be wire brushed and cleaned and in the case of iron products, a coat of approved protective paint applied to these surfaces. When corrosion is from the effects of hot solder paste, the areas shall be cleaned and polished and a wash of bicarbonate of soda and water used to neutralize the acid condition.
- E. Instructions: On completion of the project, provide a technician familiar with the system to thoroughly instruct the Owner's representative in the care and operation of the system. The total period of instruction shall not exceed four (4) hours. The time of instruction shall be arranged with the Owner.
- F. Warranty: For a period of one (1) year after completion of the installation repair or replace any defective materials or workmanship. Upon completion of the installation, the system shall be turned over to the Owner fully inspected and tested, and in operational condition.

3.3 FIRESTOPPING

- A. Firestopping shall be performed in accordance with Specification Section on "Firestopping". All penetrations of fire-rated assemblies including walls and floors by mechanical system components (piping, ductwork, conduits, etc.) shall be firestopped as specified.

* END OF SECTION *