

Seaside Rehabilitation Center  
Portland, Maine  
For Bid  
July 18, 2014

SECTION 265100 - INTERIOR LIGHTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior lighting fixtures, lamps, and ballasts.
2. Emergency lighting units.
3. Exit signs.
4. Lighting fixture supports.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of lighting fixture, arranged in order of fixture designation. Include data on features, accessories, and finishes.
- B. Provide per unit pricing for each fixture type.

1.3 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, product(s) indicated on Drawings.

2.2 GENERAL REQUIREMENTS FOR LIGHTING FIXTURES AND COMPONENTS

- A. Recessed Fixtures: Comply with NEMA LE 4 for ceiling compatibility for recessed fixtures.
- B. Fluorescent Fixtures: Comply with UL 1598. Where LER is specified, test according to NEMA LE 5 and NEMA LE 5A as applicable.

Seaside Rehabilitation Center  
Portland, Maine  
For Bid  
July 18, 2014

- C. Metal Parts: Free of burrs and sharp corners and edges.
- D. Sheet Metal Components: Steel unless otherwise indicated. Form and support to prevent warping and sagging.
- E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

2.3 BALLASTS FOR LINEAR FLUORESCENT LAMPS

- A. General Requirements for Electronic Ballasts:
  - 1. Comply with UL 935 and with ANSI C82.11.
  - 2. Designed for type and quantity of lamps served.
  - 3. Ballasts shall be designed for full light output unless another BF, dimmer, or bi-level control is indicated.
  - 4. Sound Rating: Class A.
  - 5. Total Harmonic Distortion Rating: Less than 10 percent.
  - 6. Transient Voltage Protection: IEEE C62.41.1 and IEEE C62.41.2, Category A or better.
  - 7. Operating Frequency: 42 kHz or higher.
  - 8. Lamp Current Crest Factor: 1.7 or less.
  - 9. BF: 0.88 or higher.
  - 10. Power Factor: 0.95 or higher.
- B. Luminaires controlled by occupancy sensors shall have programmed-start ballasts.

2.4 BALLASTS FOR COMPACT FLUORESCENT LAMPS

- A. Description: Electronic-programmed rapid-start type, complying with UL 935 and with ANSI C 82.11, designed for type and quantity of lamps indicated. Ballast shall be designed for full light output unless dimmer or bi-level control is indicated:
  - 1. Lamp end-of-life detection and shutdown circuit.
  - 2. Automatic lamp starting after lamp replacement.
  - 3. Sound Rating: Class A.
  - 4. Total Harmonic Distortion Rating: Less than 20 percent.
  - 5. Transient Voltage Protection: IEEE C62.41.1 and IEEE C62.41.2, Category A or better.
  - 6. Operating Frequency: 20 kHz or higher.
  - 7. Lamp Current Crest Factor: 1.7 or less.
  - 8. BF: 0.95 or higher unless otherwise indicated.
  - 9. Power Factor: 0.95 or higher.
  - 10. Interference: Comply with 47 CFR 18, Ch. 1, Subpart C, for limitations on electromagnetic and radio-frequency interference for non-consumer equipment.

Seaside Rehabilitation Center  
Portland, Maine  
For Bid  
July 18, 2014

2.5 EXIT SIGNS

- A. General Requirements for Exit Signs: Comply with UL 924; for sign colors, visibility, luminance, and lettering size, comply with authorities having jurisdiction.

2.6 EMERGENCY LIGHTING UNITS

- A. General Requirements for Emergency Lighting Units: Self-contained units complying with UL 924.
  - 1. Charger: Fully automatic, solid-state type with sealed transfer relay.
  - 2. Operation: Relay automatically turns lamp on when power-supply circuit voltage drops to 80 percent of nominal voltage or below. Lamp automatically disconnects from battery when voltage approaches deep-discharge level. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
  - 3. Test Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
  - 4. LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.

2.7 FLUORESCENT LAMPS

- A. T8 rapid-start lamps, rated 32 W maximum, nominal length of 48 inches (1220 mm), 2800 initial lumens (minimum), CRI 75 (minimum), color temperature 3500 K, and average rated life 20,000 hours unless otherwise indicated.
- B. T8 rapid-start lamps, rated 17 W maximum, nominal length of 24 inches (610 mm), 1300 initial lumens (minimum), CRI 75 (minimum), color temperature 3500 K, and average rated life of 20,000 hours unless otherwise indicated.
- C. Compact Fluorescent Lamps: 4-Pin, CRI 80 (minimum), color temperature 3500 K, average rated life of 10,000 hours at three hours operation per start unless otherwise indicated.
  - 1. 13 W: T4, double or triple tube, rated 900 initial lumens (minimum).
  - 2. 18 W: T4, double or triple tube, rated 1200 initial lumens (minimum).
  - 3. 26 W: T4, double or triple tube, rated 1800 initial lumens (minimum).
  - 4. 32 W: T4, triple tube, rated 2400 initial lumens (minimum).
  - 5. 42 W: T4, triple tube, rated 3200 initial lumens (minimum).
  - 6. 57 W: T4, triple tube, rated 4300 initial lumens (minimum).
  - 7. 70 W: T4, triple tube, rated 5200 initial lumens (minimum).

Seaside Rehabilitation Center  
Portland, Maine  
For Bid  
July 18, 2014

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Lighting fixtures: Set level, plumb, and square with ceilings and walls. Install lamps in each fixture.
- B. Comply with NFPA 70 for minimum fixture supports.
- C. Adjust aimable lighting fixtures to provide required light intensities.
- D. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

3.2 FIELD QUALITY CONTROL

- A. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery and retransfer to normal.

END OF SECTION 265100