Reviewed for Code Compliance
Inspection Division
Portland, Maine
Date: 11/12/14

PROPOSED LIGHTING PLAN

SCALE: 1/8"=1'-0"

LIGHTING KEY NOTES

1. CONTRACTOR CHALL RELOCATE EXISTING ELECTRICAL BOX 2'-8" TO PROPERLY LOCATED LIGHT FIXTURE. VERIFY LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN.
2. CONTRACTOR SHALL ADD SECOND ELECTRICAL BOX AT EACH FIXTURE FOR MOUNTING. VERIFY LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN.
3. CONTRACTOR SHALL CONNECT RELOCATED FIXUTRES TO EXISITNG LIGHTING CRICUIT AND SWITCHING. COORDINATE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN.

LIGHTING FIXTURE SCHEDULE

A	PRESCOLITE LIGHTING 6" CAN No FT6QLIC-LB6LEDA8L35K WH 12W LED, 120V
B	FORECAST LIGHTING No F615636NV PROVIDE WITH LED LAMPS
C	FORECAST LIGHTING No 190166836 PROVIDE WITH LED LAMPS
D	SURFACE MOUNTED COLUMBIA LIGHTING No SM22-424-FAA19-4EPU-GLR PRISMAIC LENS (4) 24W, 2', T5HO 3000K
E	SURFACE MOUNTED 2 X 4 COLUMBIA LIGHTING No SM24-332-FAA19-3EPU-GLR PRISMATIC LENS (3) 32W, 4', T8, 3000K
F	FORECAST LIGHTING No F602536NV, 120V PROVIDE WITH LED LAMPS
G	FORECAST LIGHTING No FN0045836, 120V PROVIDE WITH LED LAMP
G1	WAC LIGHTING No HR-2LED--T209-27-BN 120V SHOWER LIGHT
H	FORCAST LIGHTING No F541036NI, 120V PROVIDE CFL LAMPS
I	REUSE SALVAGED FIXTURES PROVIDE LED LAMPS
J	UNDERCOUNTER LIGHT PHILLIPS LIGHTNG No 523-000028-61 120V, LED, 3000K
K	EUREKA GAUGUIN No 3442C-60 (4) 10W HAL, BIPIN, G4 BASE
L	GRID MOUNTED 2x 2 COLUMBIA LIGHTING No 4PS22-424G-SFAA19-4EPU-GLR PRISMATIC LENS (4) 24W, 2', T5HO 3000K
M	GRID MOUNTED 2x 4 COLUMBIA LIGHTING No 4PS24-328G-FAA19-3EPU-GLR PRISMATIC LENS (3) 28W, 4', T5 3000K
N	PRESCOLITE LIGHTING No LB6LEDA8L30K WH 13W LED
P	FORCAST LIGHTING No F849741 PROVIDE LED LAMPING
Q	2' COVE UPLIGHT COLUMBIA LIGHTING No COV2-232-EDU-GLR (2)32W, 4', 3000K
R	4' COVE UPLIGHT COLUMBIA LIGHTING No COV4-232-EDU-GLR, (2) 32W, 4', 3000K
S	ADVENT LIGHTING No AIP9651 (4) 4N100 BAL 120 TL BRUSHED ALUMINUM PROVIDE WITH LED LAMPS
T	ADVENT LIGHTING No AIP9652 (4) 4N100 BAL 120 TL BRUSHED ALUMINUM PROVIDE WITH LED LAMPS
X	REUSED SALVAGED CORRIDOR LIGHT

GRID MOUNTED 2x 2
COLUMBIA LIGHTING
No LSER22-30HLG-C-ED-U-GLR
LED, 3000K
LED ALTERNATE #1
GRID MOUNTED 2x 4
COLUMBIA LIGHTING
No LSER24-30HLG-C-ED-U-GLR
LED, 3000K

2' COVE UPLIGHT
FINELITE
No S11LED-2'-SO-3000K-SC-96W-120
LED ALTERNATE #1
4' COVE UPLIGHT
FINELITE
No S11LED-4'-SO-3000K-SC-96W-120

COPYRIGHT 2014
REUSE OR REPRODUCTION OF THE CONTENTS OF THIS DOCUMENT IS NOT PERMITTED WITHOUT WRITTEN PERMISSION OF FORESIDE ARCHITECTS

GENERAL NOTES:

REVISIONS:
.

BENNETT ENGINEERING
MECHANICAL • ELECTRICAL
(207) 865-9475

FORESIDE ARCHITECTS LLC
5 FUNDY ROAD
FALMOUTH, ME 04105
Phone: 207-781-3344
Fax: 207-699-5564
Online @ foresidearchitects.com

Project Status:
Permit and Bid Set

Project Number:
SRH0314

Seaside Rehabilitation and Healthcare Center
Lobby / Rehab Renovation
850 Baxter Boulevard
Portland, Maine

Drawing Name:
LOBBY PROPOSED LIGHTING PLAN

Scale:
1/8"=1'-0" OR AS NOTED

Date:
07/18/14

SHEET:
E-2.2