PLUMBING FIXTURE CONNECTION SCHEDULE

TAG	DESCRIPTION	SAN	VENT	CW	HW	GAS
P1	ADA FLUSH VALVE WC, FLOOR-MOUNTED	3"	2"	1"	-	
P1A	ADA TANK TYPE WC, FLOOR-MOUNTED	3"	2"	½"	-	
P2	SOLID SURFACE COUNTERTOP w/ INTEGRAL SINK	2"	1½"	½"	½"	
P2A	ADA WALL-MOUNTED LAVATORY	2"	1½"	½"	½"	
P3	ADA STAINLESS STEEL SINK, SINGLE BOWL	2"	1½"	½"	½"	
P4	ADA ROLL-IN SHOWER	2"	1½"	½"	½"	
P5	SALON SHAMPOO SINK	2"	1½"	½"	½"	
P6	ADA STAINLESS STEEL SINK, DOUBLE BOWL	2"	1½"	½"	½"	
P7	TUB / SHOWER UNIT	2"	1½"	½"	½"	

MINIMUM SIZE OF BELOW SLAB SANITARY & VENT PIPING SHALL BE 2".
* TEMPERED WATER FROM TMV.

General Plumbing Notes
1. Modify sprinkler piping as required for coverage of renovated / expanded areas. Provide new sprinkler heads in all renovated spaces.
R1 - Remove existing plumbing fixtures and associated piping and cap.

1 FIRST FLOOR PLAN
SCALE: 1/8" = 1'-0

COPYRIGHT 2014
REUSE OR REPRODUCTION OF THE CONTENTS OF THIS DOCUMENT IS NOT PERMITTED WITHOUT WRITTEN PERMISSION OF FORESIDE ARCHITECTS

GENERAL NOTES:

REVISIONS:
.

BENNETT ENGINEERING
MECHANICAL • ELECTRICAL
(207) 865-9475

FORESIDE ARCHITECTS LLC
5 FUNDY ROAD
FALMOUTH, ME 04105
Phone: 207-781-3344
Fax: 207-699-5564
Online @ foresidearchitects.com

Project Status:
SPEC
REVIEW SET

Project Number:
SRH0314

STATE OF MAINE
STEPHEN R. VOSE
No. 15507
LICENSED
PROFESSIONAL ENGINEER

Seaside Rehabilitation
and Healthcare Center
Lobby / Rehab Renovation
850 Baxter Boulevard
Portland, Maine

Drawing Name:
Plumbing Demolition Plan

Scale:
1/8"=1'-0"

Date:
07/18/14
Permit and Bid Set

SHEET:
P1.2

Date: 11/12/14