

SimplexGrinnell  
20 Thomas Dr.  
Westbrook, ME 04092  
Tel: 207-842-6440

## ***CERTIFICATE OF INSTALLATION***

Customer	<b>Seaside Rehab</b>
Address	850 Baxter Blvd. Portland, ME 041013
Hazard location	Lobby kitchen
System location	Ansul control box and cylinder is wall-mounted on right side of hood (facing the hood).
System Type	Ansul model R102, UL300 wet chemical per NFPA 17A & 96 and design manual UL EX 3470
System size	3-gallon (1 cylinder)
Remarks	A. System includes: (1) 3-gallon cylinders, (5) discharge nozzles, (1) fusible link detectors, (1) pull station (1) 1" mechanical gas shutoff valve and micro-switch for fire alarm connection. B. System nozzles include: (1) 1N nozzle for plenum, (1) 1W nozzle for exhaust duct , (1) 260 nozzles for the range and (1) 2120 nozzle for the griddle.
Installation date	Installation proposed for 1/30/15 but fire alarm wiring will not be complete and system will not be tested at that time.
Next inspection due	Semi-annual : October 2015, April 2016 etc.
Installed by	Installation by Bryan Ross