Inspections Division
Date: 10/25/17

S3 – Proposed Stoop Framing and Finishing (NOT TO SCALE)

Pictures shown are for reference for the shape and structure of the proposed stoop

Structure shall be:

4 posts of 4x4 PT Lumber

Beams and tread supports will be 2x8's PT Lumber

Riser height will be 7 ¼" high made from AZEK

Tread depth will be 11 ½" deep made from PT decking

Nosing shall be ¾" (home owner may decide at last minute to change Nosing to ½")

Landing will be 67" wide by 36" deep

Stair 1 will be 79" wide with wraparound of 48" long and stair 2 will be 91" wide with wraparound of 60" long