

Section 15: Solid Waste Generation

15.0 Solid Waste

Solid waste is currently stored in external receptacles, screened by wood fencing, as noted on Sheet C-2. Solid waste receptacles are hauled off-site for disposal at a licensed facility by a private waste hauler.

Using an average of 4.4 lb/person/day of solid waste, an increase of solid waste generation by 90lbs/day of solid waste is anticipated as a result of the proposed project. There are currently two dumpsters on-site, approximately 10-CY each. Whereas 10-CY dumpsters can hold approximately 4,000 lbs of waste each, no changes in solid waste disposal are proposed as a result of the proposed project. There is a location available for a third dumpster in the screened enclosure should it be necessary, or the maintenance staff can schedule more frequent solid waste removals.

Information regarding construction debris has been included in Section 9 of this application, the Construction Management Report.

