

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

FRECHETTE YRIS M & MICHAEL

Located at

836 WASHINGTON AVE

PERMIT ID: 2016-00624

ISSUE DATE: 05/04/2016

CBL: 170 B017011

has permission to **Building a 10' x 14' deck on Unit 11.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ Michael White

/s/ Laurie Leader

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

residential condominium unit

Building Inspections

Use Group: R-2 **Type:** 5B

Condominium Unit #11

ENTIRE

MUBEC/IRC 2009

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Framing Only

Final Inspection

Setbacks and Footings Prior to Pouring

Foundation/Backfill

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2016-00624	Date Applied For: 03/18/2016	CBL: 170 B017011
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Condominium Unit 11		Proposed Project Description: Building a 10' x 14' deck on Unit 11.		
Dept: Zoning Status: Approved Reviewer: Christina Stacey Approval Date: 04/26/2016		Ok to Issue: <input checked="" type="checkbox"/>		
Note: R-5 zone Lot size 46,624 sf Front yard 20' min, proposed deck >22' - OK Rear yard 20' min, proposed deck >20' - OK Side yard 8' min, proposed deck >22' - OK Lot coverage 40% = 18,649 sf max allowed, total existing & proposed 8,959 sf - OK				
Conditions:				
Dept: Building Inspecti Status: Approved w/Conditions Reviewer: Laurie Leader Approval Date: 05/04/2016		Ok to Issue: <input checked="" type="checkbox"/>		
Note:				
Conditions:				
1) Frost protection must be installed 48" minimum below grade.				
2) When a landing or deck is over 30" above a floor or grade, a guard is required at a minimum height of 36". Guardrail openings shall be less than 4". The stair rail can be 34" to 38" in height with openings less than 4-3/8", and at the open side of a stair, less than 6" is allowed at the triangle of the tread/riser at the bottom rail.				
3) Hardwired photoelectric interconnected battery backup smoke detectors shall be installed in all sleeping rooms, protecting outside these rooms, and on every level.				
The same is required for existing buildings, where permanent wiring is feasible; or at the very least battery operated smoke detectors are required. Verification of this will be upon inspection.				
4) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
5) Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to sleeping rooms. That detection must be powered by the electrical service (plug-in or hardwired) in the building and battery.				
6) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				
Dept: Fire Status: Approved w/Conditions Reviewer: Michael White Approval Date: 04/08/2016		Ok to Issue: <input checked="" type="checkbox"/>		
Note:				
Conditions:				
1) Shall meet the requirements of 2009 NFPA 1 Fire Code.				
2) All construction shall comply with City Code Chapter 10.				