P A R T I

Inspections Division

Demolition

Date: 07/12/16

1. Existing ceiling finish to remain. Cut and patch ceiling as required to facilitate construction. Paint entire ceiling at completion of repairs.
2. Existing ceiling finish finish to be removed as required for partition layouts.
3. Remove existing light fixture. Replace with new fixture as described on Electrical Plan. Reuse existing wiring as much as is permissable by code.
4. Existing light fixture and wiring to remain.
5. Existing kitchen cabinets to be configured. Remove existing countertop.
6. Existing cabinets and countertop to be removed.
7. Existing plumbing fixture to be removed. Modify water supply and drain system as required to provide service to proposed plumbing fixture.
8. Existing plumbing fixture to remain.
9. Existing cabinet and counter top to be removed.
10. Existing wood window to be removed and disposed .
11. Existing wood door to be removed and reused in noted location.
12. Existing floor finish to be removed as required for partitiona layouts.
13. Existing floor finish to remain.
14. Existing demountable partition and door system to be removed and stored in location directed by tenant.

10 Existing Conditions & Demolition Plan

0 2 6 12

GARRISON CONSULTING
41 edgewood ave
portland, maine 04103
telephone 207 450 0750
e-mail matthewwinch@earthlink.net

north plan north

LICENSED ARCHITECT MATTHEW A. WINCH STATE OF MAINE

project name
Spurwink Office Renovation

project location
901 Washington Avenue
Portland, Maine 04103

date June 17, 2016
scale 1/4" = 1'-0"
project # 2016-007
drawing title Existing Conditions & Demolition Plan
drawing number D101