



INSTALL AND TEST STORED POWER TRANSISTOR LIGHT FIXTURE ON NIGHT LIGHT CIRCUIT, LOOP UP TO 1200V/200V ON ONE CIRCUIT AND FEED FROM LISTING PANEL.

CONNECT ALL EXISTING AND EMERGENCY LIGHTING TO THE MAIN ELECTRICAL PANEL AND CONTROLS TYPICAL FOR ALL AREAS.

INSTALL AND TEST ALL EXISTING LIGHTING FIXTURES AND EXHAUST FANS SHALL BE INSTALLED WITH FIRE RATED ENCLOSURES 3" MINIMUM LARGER THAN THE EXHAUST FAN OR LIGHTING FIXTURE. FIRE RATING AND COULING OF THE FIXTURES.

EXACT LOCATION AND TYPES OF ALL LIGHTING FIXTURES, MOUNTING HEIGHTS, AND TYPES OF BALLASTS SHALL BE BROUGHT TO ARCHITECT'S ATTENTION PRIOR TO ANY WORK DONE TO THE CEILING PLANE FROM ARCHITECT FROM TO ANY WORK DONE.

ALL FLUORESCENT FIXTURES IN THE ROOMS SHALL BE DOUBLE SWITCHED. PROVIDE TANDEN BALLAST FOR THREE BULB FIXTURES IN AREAS WHERE FIXTURES ARE MOUNTED INTO INSULATED CEILING. THIS CONTRACTOR SHALL PROVIDE HOODS, 3" LARGER THAN FIXTURES IN ALL AREAS WHERE HOODS ARE MOUNTED INTO INSULATED CEILING. INSULATION INTEGRITY OF THE CEILING, SEE ARCHITECTURAL DRAWINGS FOR AREAS WHERE THESE HOODS MAY BE REQUIRED.

UNLESS NOTED OTHERWISE, ALL WIRING SHALL BE IN CONDUIT. ALL WIRING SHALL BE IN CONDUIT LONGER THAN 10FT SHALL BE AFD CU. NO EXPOSED WIRING IS ALLOWED. ALL WIRING IN BLACK WALLS SHALL BE CONCEALED, RUN IN CONDUIT.

ALL DOWNWALL LIGHTS SHALL HAVE REMOTE CONTROLLED CONTROL TO BE DETERMINED BY OWNER. CONTROLLED SHALL HAVE BY-PASS RELAYS THAT WILL COME ON UPON POWER LOSS. ROOMS SUCH AS DINING ROOMS OR LARGE ROOMS.

Revisions	No	Date
GENERAL REVISIONS	1	02/20/06
FINAL PRICING	2	07/25/06
HAD FIRST COMMITMENT	3	11/21/06

Project
THE INN AT CEDARS
 PORTLAND, MAINE
Drawing Title
ELECTRICAL FIRST FLOOR LIGHTING PLAN

Tsomidis Associates Architects and Planners
 369 Eilat Street
 Newton Upper Falls, MA 02464
 (617) 868-4774 Fax (617) 868-4783
 www.tsomidis.com

SEAL OF THE STATE OF MASSACHUSETTS
 REGISTERED PROFESSIONAL ARCHITECT
 No. 8119
 Tsomidis Associates Architects and Planners

DATE 07/25/06
SCALE 1/8" = 1'-0"
PROJECT NUMBER E-200

ZADE COMPANY INC.
 600 BROAD STREET BRISTOL, MA 02811
 TEL (617) 335-4406
 FAX (617) 451-2540
 E-MAIL: zade@zade.com