

**City of Portland, Maine – Building or Use Permit Application** 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: (207) 874-8716

Location of Construction: 640 Ocean Ave 04103		Owner: CEDARS NURSING HOME		Phone: 772-3456		Permit No: 991266	
Owner Address: 630 Ocean Ave		Lessee/Buyer's Name:		Phone:		Business Name:	
Contractor Name: **Cimino Inc.		Address: Hastbrook Warren Ave BAZELIAN No		Phone: 854-8876		Permit Issued: NOV 16 1999	
Past Use: Nursing home		Proposed Use: same		COST OF WORK: \$ 120,000		PERMIT FEE: \$ 744.00	
				FIRE DEPT. <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Denied		INSPECTION: Use Group: Type:	
Proposed Project Description: Connector Addition to Cedars				Signature: <i>[Signature]</i>		Signature: <i>[Signature]</i>	
				PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)		Zone: CBL: K-17-A-013	
				Action: Approved <input type="checkbox"/> Approved with Conditions: <input type="checkbox"/> Denied <input type="checkbox"/>		Zoning Approval: Special Zone or Reviews: <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan maj <input type="checkbox"/> minor <input type="checkbox"/> mm <input type="checkbox"/>	
Permit Taken By: K		Date Applied For: Nov. 8 1999 K				Zoning Appeal: <input type="checkbox"/> Variance <input type="checkbox"/> Miscellaneous <input type="checkbox"/> Conditional Use <input type="checkbox"/> Interpretation <input type="checkbox"/> Approved <input type="checkbox"/> Denied	

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
2. Building permits do not include plumbing, septic or electrical work.
3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

**CERTIFICATION**

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

SIGNATURE OF APPLICANT		ADDRESS:		DATE: Nov. 8 1999		PHONE:	
RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE						PHONE:	

White-Permit Desk Green-Assessor's Canary-D.P.W. Pink-Public File Ivory Card-Inspector

**PERMIT ISSUED WITH REQUIREMENTS**

**CEO DISTRICT**

*[Signature]*

COMMENTS

January 14, 2K work started.

January 28, 2K Interior work

Feb - 11, 2K started outside work

Feb - 17 2K CMU exterior wall 2/3 up.

Mar - 8 2K work going as per plans

MAR - 15 - work going well; exterior brick work started, roof being placed

10 APR. 2K work completed

Inspection Record

Type	Date
Foundation:	
Framing:	
Plumbing:	
Final: 10/APR/2K	
Other:	



CITY OF PORTLAND, MAINE  
Department of Building Inspection

# Certificate of Occupancy

LOCATION 630 Ocean Ave CBL#174-A-013

Issued to Cedars Nursing Home

Date of Issue April 10, 2000

**This is to certify** that the building, premises, or part thereof, at the above location, built — altered — changed as to use under Building Permit No. 991266, has had final inspection, has been found to conform substantially to requirements of Zoning Ordinance and Building Code of the City, and is hereby approved for occupancy or use, limited or otherwise, as indicated below.

PORTION OF BUILDING OR PREMISES

Connector Addition

APPROVED OCCUPANCY

Use group 3-B  
Type 5 A  
Boca 1996

Limiting Conditions:

This certificate supersedes  
certificate issued

Approved:

10/10/00 [Signature]

(Date)

Inspector

[Signature]

Inspector of Buildings

Notice: This certificate identifies lawful use of building or premises, and ought to be transferred from owner to owner when property changes hands. Copy will be furnished to owner or lessee for one dollar.

[Handwritten initials]  
04/11/00 [Handwritten initials]

**THIS IS NOT A PERMIT/CONSTRUCTION CANNOT COMMENCE UNTIL THE PERMIT IS ISSUED**

**Building or Use Permit Pre-Application  
Attached Single Family Dwellings/Two-Family Dwelling  
Multi-Family or Commercial Structures and Additions Thereto**

In the interest of processing your application in the quickest possible manner, please complete the Information below for a Building or Use Permit.

**NOTE\*\*If you or the property owner owes real estate or personal property taxes or user charges on ANY PROPERTY within the City, payment arrangements must be made before permits of any kind are accepted.**

Location/Address of Construction (include Portion of Building): <b>640 OCEAN AVE.</b>			
Total Square Footage of Proposed Structure <b>2000 SF</b>		Square Footage of Lot	
Tax Assessor's Chart, Block & Lot Number Chart# <b>174</b> Block# <b>A</b> Lot# <b>013</b>		Owner: <b>CEDARS NURSING HOME</b>	Telephone#: <b>772-5456</b>
Owner's Address: <b>630 OCEAN AVE PORTLAND ME.</b>		Lessee/Buyer's Name (If Applicable)	Cost Of Work: <b>\$120,000</b> Fee <b>\$744.00</b>
Proposed Project Description: (Please be as specific as possible) <b>NURSING HOME CONNECTOR ADDITION TO CEDARS</b>			
Contractor's Name, Address & Telephone <b>G.M. CIMINO INC 3 WARREN AVE WESTBROOK 04092</b>			Rec'd By <b>854-8816</b>
Current Use: <b>Nursing Home</b>		Proposed Use: <b>Same</b>	

Separate permits are required for Internal & External Plumbing, HVAC and Electrical installation.

- All construction must be conducted in compliance with the 1996 B.O.C.A. Building Code as amended by Section 6-Art I.
- All plumbing must be conducted in compliance with the State of Maine Plumbing Code.
- All Electrical Installation must comply with the 1996 National Electrical Code as amended by Section 6-Art III.
- HVAC (Heating, Ventilation and Air Conditioning) installation must comply with the 1993 BOCA Mechanical Code.

You must Include the following with you application:

- 1) A Copy of Your Deed or Purchase and Sale Agreement
- 2) A Copy of your Construction Contract, if available
- 3) A Plot Plan/Site Plan

Minor or Major site plan review will be required for the above proposed projects. The attached checklist outlines the minimum standards for a site plan.

**4) Building Plans**

**Unless exempted by State Law, construction documents must be designed by a registered design professional.**

A complete set of construction drawings showing all of the following elements of construction:

- Cross Sections w/Framing details (including porches, decks w/ railings, and accessory structures)
- Floor Plans & Elevations
- Window and door schedules
- Foundation plans with required drainage and dampproofing
- Electrical and plumbing layout. Mechanical drawings for any specialized equipment such as furnaces, chimneys, gas equipment, HVAC equipment (air handling) or other types of work that may require special review must be included.


**Certification**

I hereby certify that I am the Owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this permit at any reasonable hour to enforce the provisions of the codes applicable to this permit.

Signature of applicant: 	Date: <b>11/3/99</b>
---	----------------------

Building Permit Fee: \$30.00 for the 1st \$1000. cost plus \$6.00 per \$1,000.00 construction cost thereafter.

Additional Site review and related fees are attached on a separate addendum



# BUILDING PERMIT REPORT

DATE: 9 NOV, 99 ADDRESS: 640 OCEAN AVE. CBL: 174-A-013

REASON FOR PERMIT: Addition of Connector between old & New.

BUILDING OWNER: Cedars Nursing Home

PERMIT APPLICANT: \_\_\_\_\_ CONTRACTOR C. Mingo Inc.

USE GROUP: R-2 CONSTRUCTION TYPE: 5A CONSTRUCTION COST: \$120,000 PERMIT FEES: \$744.00



The City's Adopted Building Code (The BOCA National Building code/1996 with City Amendments)  
The City's Adopted Mechanical Code (The BOCA National Mechanical Code/1993)

## CONDITION(S) OF APPROVAL

This permit is being issued with the understanding that the following conditions are met: \*1, \*2, \*22, \*32, \*34  
21, 22, 23

1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
2. Before concrete for foundation is placed, approvals from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection) **"ALL LOT LINES SHALL BE CLEARLY MARKED BEFORE CALLING."**
3. Foundation drain shall be placed around the perimeter of a foundation that consists of gravel or crushed stone containing not more than 10 percent material that passes through a No. 4 sieve. The drain shall extend a minimum of 12 inches beyond the outside edge of the footing. The thickness shall be such that the bottom of the drain is not higher than the bottom of the base under the floor, and that the top of the drain is not less than 6 inches above the top of the footing. The top of the drain shall be covered with an approved filter membrane material. Where a drain tile or perforated pipe is used, the invert of the pipe or tile shall not be higher than the floor elevation. The top of joints or top of perforations shall be protected with an approved filter membrane material. The pipe or tile shall be placed on not less than 2" of gravel or crushed stone, and shall be covered with not less than 6" of the same material. Section 1813.5.2
4. Foundations anchors shall be a minimum of 1/2" in diameter, 7" into the foundation wall, minimum of 12" from corners of foundation and a maximum 6' O.C. between bolts. Section 2305.17
5. Waterproofing and damp proofing shall be done in accordance with Section 1813.0 of the building code.
6. Precaution must be taken to protect concrete from freezing. Section 1908.0
7. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
8. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of 1/2 inch gypsum board or the equivalent applied to the garage means of 1.2 inch gypsum board or the equivalent applied to the garage side. (Chapter 4, Section 407.0 of the BOCA/1996)
9. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993). Chapter 12 & NFPA 211
10. Sound transmission control in residential building shall be done in accordance with Chapter 12, Section 1214.0 of the City's Building Code.
11. Guardrails & Handrails: A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42", the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42", except Use Group R which is 36". In occupancies in Use Group A,B,H-4, I-1, I-2, M and R and public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect. (Handrails shall be a minimum of 34" but not more than 38". Use Group R-3 shall not be less than 30", but not more than 38"). Handrail grip size shall have a circular cross section with an outside diameter of at least 1 1/4" and not greater than 2". (Sections 1021 & 1022.0). Handrails shall be on both sides of stairway. (Section 1014.7)
12. Headroom in habitable space is a minimum of 7'6". (Section 1204.0)
13. Stair construction in Use Group R-3 & R-4 is a minimum of 10" tread and 7 3/4" maximum rise. All other Use Group minimum 11" tread, 7" maximum rise. (Section 1014.0)
14. The minimum headroom in all parts of a stairway shall not be less than 80 inches. (6'8") 1014.4
15. Every sleeping room below the fourth story in buildings of Use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension shall be 20 inches (508mm), and a minimum net clear opening of 5.7 sq. ft. (Section 1010.4)
16. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units. (Section 1010.1)
17. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hour, including fire doors with self closer's. (Over 3 stories in height requirements for fire rating is two (2) hours. (Section 710.0)
18. The boiler shall be protected by enclosing with (1) hour fire rated construction including fire doors and ceiling, or by providing automatic extinguishment. (Table 302.1.1)

19. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 920.3.2 (BOCA National Building Code/1996), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):
  - In the immediate vicinity of bedrooms
  - In all bedrooms
  - In each story within a dwelling unit, including basements
20. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type. (Section 921.0)
21. The Fire Alarm System shall maintained to NFPA #72 Standard.
22. The Sprinkler System shall maintained to NFPA #13 Standard.
23. All exit signs, lights and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023.0 & 1024.0 of the City's Building Code. (The BOCA National Building Code/1996)
24. Section 25 – 135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".
25. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification the Division of Inspection Services.
26. Ventilation shall meet the requirements of Chapter 12 Sections 1210.0 of the City's Building Code. (Crawl spaces & attics).
27. All electrical, plumbing and HVAC permits must be obtained by a Master Licensed holders of their trade. No closing in of walls until all electrical (min. 72 hours notice) and plumbing inspections have been done.
28. All requirements must be met before a final Certificate of Occupancy is issued.
29. All building elements shall meet the fastening schedule as per Table 2305.2 of the City's Building Code (The BOCA National Building Code/1996).
30. Ventilation of spaces within a building shall be done in accordance with the City's Mechanical code (The BOCA National Mechanical Code/1993). (Chapter M-16)
31. Please read and implement the attached Land Use Zoning report requirements.
32. Boring, cutting and notching shall be done in accordance with Sections 2305.3, 2305.3.1, 2305.4.4 and 2305.5.1 of the City's Building Code.
33. Bridging shall comply with Section 2305.16.
34. Glass and glazing shall meet the requirements of Chapter 24 of the building code. (Safety Glazing Section 2405.0)
35. All signage, shall be done in accordance with Section 3102.0 signs of the City's Building Code, (The BOCA National Building Code/1996).

  
 E. Samuel Hoffses, Building Inspector  
 Cc: M. McDougall, PFD  
 Marge Schmuckal, Zoning Administrator  


PSH 10/25/99

**\*\*On the basis of plans submitted and conditions placed on these plans any deviations shall require a separate approval.**

12-9-99

TO: SAM HOFFER

FROM: RICK KNOWLTON

RE: CGOARW, OCEAN AVE

RECENTLY WE DID A SITE INSPECTION OF THE  
CGOARW PROJECT ON OCEAN AVENUE. WE WOULD HAVE  
NO OBJECTION TO A CERTIFICATE OF OCCUPANCY BEING  
ISSUED FOR THIS PROJECT.

## Drawing Notes

Progress 4-21-99

- 01-1 Alternates:  
#1. Multi-purpose room, including exterior walls, new ceiling, etc.  
#2. Provide air conditioning to existing Central Kitchen.
- ~~02-1~~ Remove existing exterior wall.
- 02-2 Remove existing door, frame and hardware. Close opening with brick veneer, metal stud and g.wb. to match existing.
- 03-1 Provide cementitious leveling compound to create floor level with existing interior floor slab.
- ~~03-2~~ New precast concrete lintels and sills, match existing.
- 04-1 Brick veneer, match existing.
- 06-1 Provide wall and base cabinets, see int. elev.
- 06-2 NOT USED
- ~~07-1~~ Gutter (match existing), scupper, downspout and concrete splashblock.
- ~~07-2~~ Remove gravel stop, tie in new roofing to existing.
- 08-1 NOT USED
- ~~08-2~~ Relocate(d) existing window, frame and hardware as indicated.
- 08-3 Provide new pair 3'-0" wide hollow metal doors, frame and hardware, 1 hour fire rated with lever handle lockset, closers, armor plates, astragal, panic devices????,
- 09-1 NOT USED
- 10-1 Provide corner guards from top of base to 5'-0" above floor.
- ~~15-1~~ Connect water and waste from soda dispenser, coffee makers to existing underslab piping at toilet room.
- ~~15-2~~ Heat to be provided by recessed ceiling mounted unit heaters.
- ~~16-1~~ Relocate(d) light fixture.




# Progress Print


# 4-21-99

## DOOR SCHEDULE

Door No.	Door Size 6'-8" HIGH	Hdw Set	Door			Frame		Detail			Fire Rating Label	Remarks
			Thk	Matl	Type	Matl	Type	Jmb	Hd	Sill		
CC1	PAIR 3'-0"		1 3/4"	S.C. WD	VW	HM	SEE DTL.				120 MIN.	
CC2	3'-0"	X	↓	↓	↓	↓						VERIFY FIT IN EXISTING M.O.
CC3	PAIR 3'-0"		↓	↓	↓	↓						
CC4	3'-8"		↓	↓	↓	↓					90 MIN.	ALT. #1

## DOOR TYPES






PROGRESS PRINT  
APRIL 21, 1999

1

**PLAN DETAILS AT COLUMN. ENCL.**

1 1/2" = 1'-0"

Standa  
Scale



2

TYPICAL WALL SECTION

1/2" = 1'-0"

Progress Print

4-21-99