

Replace 40' run of existing, aging stockade cedar fence, 6' tall, with new Board + Lattice cedar fence, 8' tall, in the same location. New fence will use 12' posts, 4' in the ground; straight run across flat ground.

Maine Line Fence, materials

6' plus 2' Board and Lattice Panel	\$247.00x5	\$1,235.00
12' Posts 5"x5" Cedar with a Chamfer Top.	\$88.00x6	\$528.00
Delivery		\$60.00
Robin's Property Services, labor		<u>\$1,120.00</u>
	TOTAL	\$2,943.00

Similar fence:

