

# A.J. Levesque Excavation LLC

115 Mountainside Drive

Turner, Maine

Phone: (207) 576-7727

Subconcrators:

T.K. Concrete (concrete pouring)

Portland Sand & Gravel (utility tie-ins)

●●●●● 4" Perforated drain tile covered with 3/4 stone and fabric

Concrete walls: set on 8" by 18" footing, includes all footing pads.

Walls to have two continuous rows of #4 rebar and are 8" thick 7' 10" high.

Windows: 3 standard 8" vinyl windows with a bulkhead, 4" finished floor over 6 mil poly with saw cut control joints.

Foundation damp proofing provided.

Under house slab: 8" (or footing height) 3/4" stone

