Inspections Division
Date: 05/16/14

DOOR AND FRAME SCHEDULE

MARK	DOOR SIZE WD	DOOR SIZE HGT	DOOR SIZE THK	DOOR MATL	DOOR GLAZING	DOOR LOUVER WD	DOOR LOUVER HGT	FRAME MATL	FRAME EL	FRAME DETAIL HEAD	FRAME DETAIL JAMB	FRAME DETAIL SILL	FIRE RATING LABEL	HARDWARE SET NO	HARDWARE KEYSIDE RM NO	NOTES
1	2'-8"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	Existing to remain
2	2'-4"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--
3	5'-4"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--
4	1'-10"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--
5	4'-6"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--
6	2'-8"	6'-8"	NA	--	--	0"	0"	--	--	--	--	--	--	--	--	--
7	2'-8"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--
9	2'-0"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--
10	2'-0"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--
11	2'-4"	6'-8"	1 3/4"	--	--	0"	0"	--	--	--	--	--	--	--	--	--

3RD FLOOR REMOVED FROM SCOPE OF WORK

WINDOW SCHEDULE

MARK	SIZE WIDTH	SIZE HEIGHT	TYPE	MATERIAL	NOTES
1	2'-8"	5'-4"	--	--	--
2	2'-8"	5'-4"	--	--	--
3	2'-8"	5'-4"	--	--	--
4	2'-2"	3'-6"	--	--	--
6	2'-8"	5'-4"	--	--	--
7	2'-8"	5'-4"	--	--	--
8	2'-8"	5'-4"	--	--	--
9	2'-2"	4'-6"	--	--	--
10	2'-2"	4'-6"	--	--	--
11	2'-8"	2'-10"	?	?	--
11	1'-6"	2'-0"	--	--	--
12	2'-8"	2'-10"	--	--	--

3RD FLOOR REMOVED FROM SCOPE OF WORK

DRAWN: 02.21.14
REVISED: 03.28.14
3RD FLOOR REMOVED FROM SCOPE OF WORK
REVISED 05.03.14
TEMPERED GLASS ADDED ON WINDOW #5

PROSPECT
DESIGN
58 FORE ST. PORTLAND, ME
www.prospectdesign.me
T: 207 - 749 - 7400

DATE: 5.8.2014
DRAWN BY: BB

SCHEDULE
COOK BOGGIATTO

A-6.1