



TYPICAL ROOF ASSEMBLY (R-52 MIN)
 ASPHALT SHINGLES
 BUILDING WRAP AIR BARRIER
 2 3/8" NAILER ROOF PANEL (R-12 MIN)
 EXT. SEAMS TAPED W/ BUILDING WRAP TAPE
 INT. GAPS FILLED W/ SPRAY FOAM
 WOOD TRUSS TOP CHORD W/
 12" FIBERGLASS BATT INSULATION (R-38 MIN)
 AIR SPACE
 WOOD TRUSS BOTTOM CHORD
 FURRING CHANNELS
 POLY VAPOR BARRIER
 3/8" GWB

TYPICAL WALL ASSEMBLY (R-31 MIN)
 FIBER-CEMENT SIDING (SEE ELEVATIONS)
 BUILDING WRAP AIR BARRIER
 2 3/8" NAILER WALL PANEL (R-12 MIN)
 EXT. SEAMS TAPED W/ BUILDING WRAP TAPE
 INT. GAPS FILLED W/ SPRAY FOAM
 2X6 WOOD FRAMING W/
 5/8" BATT INSULATION (R-19 MIN)
 POLY VAPOR BARRIER
 3/8" GWB

FOUNDATION WALL - SEE STRUCTURAL
 2" RIGID INSULATION (R-12 MIN)

KEY
 - - - - - CONTINUOUS CONNECTION BETWEEN ROOF AIR BARRIER, WALL AIR BARRIER, AND SLAB VAPOR BARRIER.

10 KITCHEN BUILDING SECTION
 0 2'-0" SCALE: 1/2" = 1'-0"

Bild Architecture
 PO Box 8235
 Portland, ME
 04104
 207.408.0188
 evan@bildarchitecture.com

ARCHITECTURE

LICENSED ARCHITECT
 EVAN A. CARROLL
 No. 3687
 STATE OF MAINE
 3/13/13

PROJECT NO.
12019
 PROJECT NAME
**GMS. WESTMINSTER HOME
 PORTLAND, ME**

CONSTRUCTION DOCUMENTS

DRAWN BY
EAC
 SHEET TITLE
KITCHEN SECTION

ISSUE DATE
03.13.13
 SHEET SCALE
1/2" = 1'-0"