



Below are the Specifications And Materials that you have selected for your deck.

Overview	Number of Levels: 1	Footer Depth: 24" 48"
	Total Square Feet: 64	Live Load: 96 Dead Load: 10

Component	Size	Wood Type
Joists	2x8	Top Choice Treated
Beams	2x8	Top Choice Treated
Posts	6x6	Top Choice Treated
Decking	5/4x6	Pressure Treated
Railing		
Lattice		

FooterDepth	24" 48"	Live Load	96 psf
		Dead Load	10 psf



Material List

Lumber Materials					
Item#	Qty	Description	Usage	Unit Cost	Cost
468938	13	Top Choice #2 Prime Pressure Treated Lumber (Common: 2 x 8 x 8; Actual: 1.5-in x 7.25-in x 96-in)	Beam	7.57	98.41
468942	4	Top Choice #2 Prime Pressure Treated Lumber (Common: 2 x 10 x 8; Actual: 1.5-in x 9.25-in x 96-in)	Cladding	9.27	37.08
468972	17	5/4 x 6 x 8-ft Premium Treated Decking	Decking	5.80	98.60
468960	1	#2 Pressure Treated Lumber (Common: 6 x 6 x 8; Actual: 5.5-in x 5.5-in x 96-in)	Post	21.77	21.77

Other Materials					
Item#	Qty	Description	Usage	Unit Cost	Cost
116239	10	USP 2-in x 8-10-in Triple Zinc Slant Nail Joist Hanger	Joist Framing	1.11	11.10
184955	1	USP 1 lb 9-Gauge 1-1/2-in Galvanized Smooth Joist Hanger	Joist Framing	4.88	4.88
69139	2	Grip-Rite 1 lb 9-Gauge 3-in Hot-Dipped Galvanized Smooth Nails	Joist Framing	3.87	7.74
37164	4	USP1-5/16-in x 2-3/8-in x 6-15/16-in Triple Zinc Angle Clip	Joist Framing	3.11	12.44
21993	14	USP 1-1/2-in x 6-1/2-in Triple Zinc Rafter Tie	Joist Framing	0.58	8.12
68408	1	USP 1 lb 11-Gauge 1-1/2-in Hot-Dipped Galvanized Smooth Joist Hanger Nails	Joist Framing	4.88	4.88
10385	10	QUIKRETE 80 lbs Setting Post Concrete Mix	Footing to Post	3.80	38.00
10150	2	QUIKRETE 12-in Concrete Forming Tube	Footing to Post	9.22	18.44
193212	4	The Hillman Group 1/2-in x 10-in HDG Anchor Bolt	Footing to Post	1.16	4.64
69141	1	1 lb 8-Gauge 3-1/2-in Hot-Dipped Galvanized Smooth Nails	Footing to Post	3.87	3.87
6472	4	USP 6-in x 6-in Steel G185 Post Base	Footing to Post	19.98	79.92
163411	16	USP 6-in x 6-in Steel G185 Post Cap	Post to Beam	4.43	70.88
17365	2	1 lbs #8 x 2-1/2-in Countersinking-Head Galvanized Deck Screws	Deck Planking	8.47	16.94

Total Cost Without Tax:				537.71	
-------------------------	--	--	--	--------	--